Viz World User Guide

Version 17.0

Disclaimer

Vizrt provides this publication "as is" without warranty of any kind, either expressed or implied. This publication may contain technical inaccuracies or typographical errors. While every precaution has been taken in the preparation of this document to ensure that it contains accurate and up-to-date information, the publisher and author assume no responsibility for errors or omissions. Nor is any liability assumed for damages resulting from the use of the information contained in this document. Vizrt's policy is one of continual development, so the content of this document is periodically subject to be modified without notice. These changes will be incorporated in new editions of the publication. Vizrt may make improvements and/or changes in the product (s) and/or the program(s) described in this publication at any time. Vizrt may have patents or pending patent applications covering subject matters in this document. The furnishing of this document does not give you any license to these patents.

Technical Support

For technical support and the latest news of upgrades, documentation, and related products, visit the Vizrt web site at www.vizrt.com.

Created on

2019/03/11

Contents

This is the user guide for Viz World Client and Server.

This guide is designed to fit people with no or little experience in using Viz World, and aims to help new users become familiar with the system.

1 Related Documents

For additional information, see the following documents:

- Viz World Classic User Guide: Contains information on how to create map templates using Viz World Classic.
- Viz World Plug-ins Guide: Contains information on how to use the Viz World plug-ins.
- Viz Artist User Guide: Contains information on how to create graphics scenes and animations in Viz Artist.
- Viz Engine Administrator Guide: Contains information on how to install the Viz Engine software and supported hardware. Viz Engine is the output engine used for playout of graphics, video, images, SDI sound and sound effects.
- Viz Trio User Guide: Contains information on how to create real-time character generated content based on templates and how to play out pages in shows based on these templates..
- Viz Pilot User Guide: Contains information on how to create content based on templates and how to play out elements in playlists based on these templates.
- Viz Multichannel User Guide: Describes how to install, configure and use Viz Multichannel.
- Viz NLE Administrator Guide: Contains information on how to use your graphics in a non-linear editing tool.
- Viz Weather User Guide: Contains information on how to create real-time generated weather information and interactive shows using branded maps.

For more information about all of the Vizrt products, visit:

- www.vizrt.com
- Vizrt Documentation Center
- Viz University

2 Feedback And Suggestions

We encourage suggestions and feedback about our products and documentation. To give feedback and/or suggestions, please contact your local Vizrt customer support team at www.vizrt.com.

See Also

- About Viz World

3 Introduction

This is the user guide for Viz World Client and Server.

This guide is designed to fit people with no or little experience in using Viz World, and aims to help new users become familiar with the system.

3.1 Related Documents

For additional information, see the following documents:

- Viz World Classic User Guide: Contains information on how to create map templates using Viz World Classic.
- Viz World Plug-ins Guide: Contains information on how to use the Viz World plug-ins.
- Viz Artist User Guide: Contains information on how to create graphics scenes and animations in Viz Artist.
- Viz Engine Administrator Guide: Contains information on how to install the Viz Engine software and supported hardware. Viz Engine is the output engine used for playout of graphics, video, images, SDI sound and sound effects.
- Viz Trio User Guide: Contains information on how to create real-time character generated content based on templates and how to play out pages in shows based on these templates..
- Viz Pilot User Guide: Contains information on how to create content based on templates and how to play out elements in playlists based on these templates.
- Viz Multichannel User Guide: Describes how to install, configure and use Viz Multichannel.
- Viz NLE Administrator Guide: Contains information on how to use your graphics in a non-linear editing tool.
- Viz Weather User Guide: Contains information on how to create real-time generated weather information and interactive shows using branded maps.

For more information about all of the Vizrt products, visit:

- www.vizrt.com
- Vizrt Documentation Center
- Vizrt Training Center
- Vizrt Forum

3.2 Feedback And Suggestions

We encourage suggestions and feedback about our products and documentation. To give feedback and/or suggestions, please contact your local Vizrt customer support team at www.vizrt.com.

See Also

- About Viz World

4 About Viz World

For many years **Viz World Classic** (formerly called Viz Curious Maps) was the broadcast industry's number one tool for the creation of branded 2D maps and geographic animations.

Now **Viz World** takes this to a new level by adding support for real-time 3D maps and adding the option to extend it to a client-server solution.

Viz World takes branded map imagery and provides it to different clients that are embedded within Vizrt's control applications like Viz Trio and Viz Pilot. Templates created within Viz World can also be accessed by Viz Weather, Viz Artist, and even NLE systems.

This tight integration allows users to seamlessly create branded, animated maps and add them to graphic templates or insert them directly into a 3D scene. In addition, high-resolution satellite imagery from around the world can instantly be browsed, downloaded and incorporated.

Viz World Client (WoC) integrates Viz World's mapping ability and database into Viz Artist and Viz Engine graphics. By utilizing a set of geographic referencing plugins and the maps produced by WoC, the creation of location based graphics using maps, 3D objects, texts, and so on, is seamless.

WoC includes a set of Viz Artist plugins and the Viz World World Map Editor (WME). The editor is integrated into Vizrt products, simplifying production and control of the graphics.

The WoC also includes the Map Designer for creating map templates on-the-fly, as well as the Map Builder for creating animated scenes with single or multiple destinations.

Usage of WoC clients requires one or more **Viz World Servers** (WoS) installed, running and connected to the network. WoS is a software module used for creating template based maps and managing client requests. All the map styles, map projects and designs are stored on the server. The server's license determines the number of concurrent client connections and the available data sets.

This section contains information on the following topics:

- Workflow
- New Features

4.1 Workflow

The basic workflow from design of templates to playout is as follow:

1. First step of the process is to create a single (or multiple) in-house map project template that sets the look and feel of all the produced maps later in the production chain. This is done using Viz World Classic (VWC), selecting for example style and color on the selected map area, type of border lines, label fonts and available marker icons.
2. The designed map project template is made available to users of Vizrt client software via the Viz World Server (WoS).
3. A graphic designer creates Viz scenes that include maps, based on the same map project template now residing on the Viz World Server. The designer has the option to create 2D or 3D labels and markers inside Viz, instead of using the ones exposed in Viz World Classic.
4. Based on the Viz scenes, graphical templates can be made for other Vizrt applications.
5. An editor opens a template, from for example the Viz Pilot or Viz Weather system, and creates a map to fit the main news or weather story of today.

4.2 New Features

- Google Maps integration
    - Google tiles based on predefined profiles or user profiles
    - Google search engine

- UAC awareness
    - On a clean install, all user files are saved under C:\ProgramData\vizrt\VizWorld
    - When upgrading, user files are saved in the old location
    - VizWorldUACMigrationAssistant.exe can be found in the program folder to help the migration to UAC aware.

5 Requirements

This section describes the prerequisites such as the licensing, software and hardware requirements.

This section contains information on the following topics:

- License Requirements
- Software Requirements
- Server System Requirements
- Ports and Connections

See Also

- Installation
- Configuration

5.1 License Requirements

The following licenses are needed to run Viz World Server and Viz Engine:

- A USB dongle license for Viz World Server
- A USB dongle license for Viz Engine

If you are using the **old green Sentinel dongles**, please update your Sentinel Super Pro drivers to the latest version. If you are using the **Aladdin dongles** (usually blue), please install the Aladdin Hard Lock driver.

Aladdin dongle driver is available in "Installers" folder in the installation directory, which is by default in the following path:

- **32 bit**: `C:\Program Files (x86)\vizrt\Viz World\Installers`
- **64 bit**: `C:\Program Files\vizrt\Viz World\Installers`

> ⚠ **Note:** Viz World Server is a feature included in the license file. If the server has additional features enabled, make sure the new license file covers those features as well.

5.2 Software Requirements

To run the **Viz World Client and Server**, the following software is required:

- Viz World Client (Map Editor) 17.0
- Viz World Server 17.0 - It is recommended to install the server on a separate machine.
- Viz World database 17.0
- Microsoft Visual C++ 2010 Redistributable Package

- Microsoft .NET Framework 4 or later is required for the Map Designer, Map Builder and World Map Editor.

For **graphics design** the following software and version numbers are needed.

- Viz Artist 3.6 or later

For a **newsroom/control room** the following application versions are required:

- Viz Trio 2.12 or later
- Viz Pilot 5.7 or later
- Media Sequencer 1.23 or later

5.3 Server System Requirements

Minimum configuration:

- **CPU**: Intel Core2 CPU, 2.0 GHz
- **Memory:** 4GB
- **Hard disk space:** A full installation requires about 2 GB free disk space. Optional data packages will require between 4GB to 500GB free disk space.

Recommended configuration:

- **CPU:** 2 x Intel i7 CPU (or equivalent Intel Xeon processor)
- **Memory:** 16GB
- **Hard disk space:** A full installation requires about 2GB free disk space. Optional data packages will require between 4GB to 1000GB free disk space.

> ⚠ **Note:** When more than one server will be run on a single machine it is necessary to use the recommend system configuration described above. See Server Allocator Configuration.

Server Operating Systems:

- Microsoft Windows 7/10 (64-bit, 32-bit)
- Windows Server 2008R2/2012R2/2016

Also note that fast and multiple CPU cores are the most important component of WoS.

5.4 Ports And Connections

The following describes all connections and default listening port numbers that are important for any system/network administrator to know of. However, it is, if possible, recommended to run the system on a network without firewalls.

102 (TCP) is a Viz World Server listener port for Viz World Client connections when Server Allocator is not in use or only has one Viz World Server running.

103 (TCP) is a Viz World Server listener port for configuration tool connections to the first Viz World Server instance (as configurations are controlled by the first server instance).

10100 (TCP) is a Server Allocator listener port for Viz World Client connections, and is only used in order for clients to get connection details about Viz World Server(s). The first client connection will

always be diverted to port 102. In case of Multiple server instances port numbers are assigned according to a predefined schema. In case there is no Server Allocator, Viz World Server will itself switch to port 102.

10100 (UDP) is a Viz World Server listener port for Server Allocator communication.

10200 (UDP) is a Server Allocator listener port for Viz World Server communication.

Both UDP ports are internal ports used between the servers.

5.4.1   Multiple server instances

If a machine is running multiple Viz World Server instances every extra instance (second and above) opens other ports by this formula:

- Viz World Server listener port (TCP): **10100 + ID − 1**.
- Server Allocator listener port (UDP): **10200 + ID − 1** (this is an internal port between servers) (where ID indicates the instance, e.g. 3rd server, ID = 3).

If four Viz World Server instances are configured, the following listener ports will be used:

- 102 (TCP): 1st instance
- 10101 (TCP): 2nd instance
- 10102 (TCP): 3rd instance
- 10103 (TCP): 4th instance
- 10100 (TCP) : Viz World Client(s) connection to the Server Allocator.
- 103 (TCP): Configuration tool connection to the Viz World Server.

Internal ports used by Server Allocator and Viz World Server(s) to communicate between themselves:

- 10100 (UDP): Server Allocator
- 10200 (UDP): 1st instance
- 10201 (UDP): 2nd instance
- 10202 (UDP): 3rd instance
- 10203 (UDP): 4th instance

6 Installation

This section describes how to install and remove the components of Viz World Server (WoS) and Viz World Client (WoC).

This section contains information on the following topics:

- Downloading the software
- Installing Viz World Server
- Installing Viz World Client
- Installing Photoshop Plugin

6.1 Downloading The Software

Whilst you have an active map support contract, you have a personal login to the Vizrt FTP server (first year support is included).

- Download the software from the Vizrt FTP at ftp://download.vizrt.com/ under the Viz World folder.

> ⚠ **Note:** You will need to use an FTP Client to access this site and not a regular web browser.

Please use the FTP server to find the latest Vizrt software releases, documentation, help files, drivers and more. You can also use the FTP to upload and exchange files with Vizrt

6.2 Installing Viz World Server

> ⚠ **Note:** Before starting an installation, ensure that the Viz World Server USB license dongle and license file are available. unless the license is MAC address based license then only license file is required.

The Viz World Data and Viz World Server installers are required.

This section contains information on the following topics:

- To install Viz World Data
- To install Viz World Server and Classic

6.2.1 To install Viz World Data

1. Start the Viz World Data installer VizWorldDb17.0.0.msi
2. Click **Next**
3. Select the features to install, where "Combination" and "Relief" are mandatory features and Extras is optional (Extras feature contains UK MapData with Metropolitan counties of England to be imported as street data if required)
4. Click **Install** to begin the installation
5. Click **Finish**

6.2.2 To install Viz World Server and Classic

Before Viz World Classic is installed, you have To install Viz World Data

> ⚠ **Note:** Exit all Windows programs before running the Setup Program.

1. Start the Viz World Server installer VizWorld17.0.0.msi
2. Click **Next**
3. Read the End-User license agreement and accept it
4. Click **Next**
5. Select destination directory, and click **Next.** Default installation directory is:
    - 32 bit: C:\Program Files (x86)\Curious Software\Curious World Maps
    - 64 bit: `C:\Program Files\vizrt\Viz World`
6. Click **Install** to start the installation
7. Click **Finish**
8. *Optional*: Install QuickTime if it is not previously installed.
    - If a newer version of QuickTime is installed the installation will be stopped.

> ⚠ **Tip:** If you do not already have QuickTime installed you can download the installer from the Apple website.

6.3 Installing Viz World Client

Viz World Client (WoC) is used to integrate maps and geographical data into scenes. Its components are the Map Designer , Map Builder, World Map Editor, Map Editor Classic and design plugins.

Viz World Client (WoC) installs new components in the following places (if Viz Engine is already installed).

- Viz 3.x (`C:\Program Files\vizrt\viz3`)
- Common files (`C:\Program Files\vizrt\common`) (components are installed here only if Viz Engine is not installed)

Select the installer settings that correspond to your Viz Engine (ie. 32 or 64-bit).

Use the bundle installer (which includes both 32 and 64-bit) for easier installation of Viz Trio/Viz Pilot/Viz Weather clients when combining with a 64-bit Viz Engine.

There are two ways of installing the client; a standard installation which requires the user to perform and confirm all actions during the installation, or a silent installation that enables the user to install Viz World Client without using the installer's dialog boxes.

This section contains information on the following topics:

- To install Viz World Client
- To install/uninstall Viz World Client in silent mode
- To remove Viz World Client

6.3.1   To install Viz World Client

1. Double-click the *VizWorldClient_17x.x.x.msi* installer to start the installation
2. In the Setup Type window, select **Typical**, and click Next
3. Select the **Yes, I want to restart my computer now** option
4. Click Finish.

6.3.2   To install/uninstall Viz World Client in silent mode

Viz World Client 64bit silent install:

WHEN Viz ENGINE 64bit IS ALREADY INSTALLED:

- Command: msiexec /i <path to Viz World Client installer file> /passive (This will install Viz World Client 64bit including Viz files to "C:\Program Files\Vizrt\Viz3\plugin" and design client, help files and API files to "C:\Program Files\Vizrt\Common")
  Example: msiexec /i C:\VizWorldClient_x64_17.0.0.14934.msi /passive
- Command: msiexec /i <path to Viz World Client installer file> /passive ADDLOCAL=ALL (This will install Viz World client 64bit including Viz files to "C:\Program Files\Vizrt\Viz3\plugin" and all client files (Design-Admin-Traffic), help files and API files to "C:\Program Files\Vizrt\Common\Maps")
  Example: msiexec /i C:\VizWorldClient_x64_17.0.0.14934.msi /passive ADDLOCAL=ALL
- Command: msiexec /i <path to Viz World Client installer file> /passive ADDLOCAL=ALL REMOVE=Admin (This will install Viz World client 64bit including Viz files to "C:\Program Files\Vizrt\Viz3\plugin" and client files (Design-Traffic), help files and API files to "C:\Program Files\Vizrt\Common\Maps")
  Example: msiexec /i C:\VizWorldClient_x64_17.0.0.14934.msi /passive ADDLOCAL=ALL REMOVE=Admin
- REMOVE key values are :
  "Design" (not to install Map Design Client, OSM Downloader, Style editor)
  "Admin" (not to install Map config client, World server Monitor, Maps Name Editor, GeoFeeds Configuration, CMS Test Client)
  "Traffic" (not to install FetchTraffic and TotalTrafficConfigurator)
  "H" (not to install help files)
  "A" (not to install API files)
- Command: msiexec /i <path to Viz World Client installer file> /passive ADDLOCAL=ALL VIZFOLDER=<path> (This will install Viz World client 64bit including Viz files to the specified path and client files (Design-Admin-Traffic), help files and API files to "%\Program Files\Vizrt\Common\Maps")
  Example: msiexec /i C:\VizWorldClient_x64_17.0.0.14934.msi /passive ADDLOCAL=ALL VIZFOLDER=c:\temp

WHEN Viz ENGINE 64bit IS NOT ALREADY INSTALLED:
Same as when Viz Engine 64bit is installed except that Viz files will not be deployed.

Viz World Client 32bit silent install:

WHEN Viz ENGINE 32bit IS ALREADY INSTALLED:

Same as Viz World Client 64bit installer, except that installation directory is "C:\Program Files (x86)\Vizrt\Common\Maps"

WHEN Viz ENGINE 32bit IS NOT ALREADY INSTALLED:

Same as when Viz Engine 32bit is installed except that Viz files will not be deployed

<u>Viz World Client 64bit/32bit silent uninstall:</u>

Command: msiexec /x <path to Viz World Client installer file> /passive

> ⚠ **IMPORTANT!** Any unexpected events during silent installation may result in a failure. Unexpected events can be, for example, needing to restart the computer or Viz not installed in the default path.

6.3.3 To remove Viz World Client

1. Start the Client installer by either:
   a. Start Add or Remove Programs and click the Change/Remove button next to the **Vizrt Viz World Client** item, or
   b. Run the *VizWorldClient_x.x.x.x.msi* installer file
2. Select the **Remove Installed Files** option and click **Next**
3. Click Finish

6.4 Installing Photoshop Plugin

The Viz World Photoshop Plugin is used to integrate Viz World and Adobe Photoshop files. Maps created with the Photoshop plugin will create a new file with separate layers for every feature and detail on the map.

The scripts which are installed as part of the plugin are used to:

· Configure the different settings of the Photoshop Plugin.
· Open Map Editor Classic to select the desired map.
· Create the final Adobe Photoshop file and layers, based on the selection and configuration.

6.4.1 Installed Files

The Photoshop plugin is installed under:

· `C:\Program Files\Adobe\Photoshop\Plug-ins\Import-Export` or
· `C:\Program Files (x86)\Adobe\Photoshop\Plug-ins\Import-Export`
  The file that is installed is

· `VizrtMapImport.8ba`
  The scripts are installed under:

· `C:\Program Files\Adobe\Photoshop\Presets\Scripts` or
· `C:\Program Files (x86)\Adobe\Photoshop\Presets\Scripts`

> ⓘ **Important**
> Newer Versions of Adobe Photoshop (like CC 2017) install in a different directory than c:
> \Program Files\Adobe\Photoshop. It might be required to copy the whole content of *c:*
> *\Program Files\Adobe\Photoshop* to the real Photoshop Installation like *C:\Program*
> *Files\Adobe\Adobe Photoshop CC 2017*

6.4.2   To install the Photoshop Plugin

1. Install Viz World Client (see Installing Viz World Client)
2. Double click the `VizWorld-Photoshop-xxx.msi`

> ⚠ **Note:** In order to support Adobe Photoshop 32 bit and 64 bit, there are two different
> installers, (i.e. x86 and x64). Ensure you have the installer which matches your
> Photoshop version, also a bundle installer is available for installing required
> dependencies, and provides the option to choose which Photoshop plugin version to
> install (i.e. x86 and x64).

3. Click Next

6.4.3   To configure the Photoshop Plugin

1. Launch Adobe Photoshop
2. Click File->Script→Viz World Setting
3. Enter the machine name of your Viz World Server

> ⓘ The configuration file being used is located in C:\Program
> Files\vizrt\Maps\Photoshop if you need to edit the configuration manually.

7 Configuration

This section describes how to configure Viz World Server, Viz Engine, and Viz Artist, as well as some useful cache settings.

This section contains information on the following topics:

- Server Configuration
- Viz Engine/Artist Configuration
- Cache Configuration

7.1 Server Configuration

The Server Configuration Tool is used to remotely configure the Viz World Server settings.

The configuration tool is included when Installing Viz World Server and can also be installed when Installing Viz World Client. From the Windows start menu, select:

- **Server:** Programs > Vizrt > Viz World Server > Server Configuration tool
- **Client:** Programs > Vizrt > Viz World Client > Server Configuration tool

> ⚠ **Caution:** The server is locked when using the configuration tool; hence, no client connection will be accepted.

> ⚠ **Note:** When using Server Allocator with multiple servers, each machine running the servers must be configured separately. Use the configuration tool to connect to all the servers and configure them.

This section contains information on the following topics:

- User Interface
- Template
- Locations
- Logins
- License
- Maps
- Standalone Clients
- Symbols
- Timeouts
- Proxy Server
- Server Logging

7.1.1   User Interface

The server configuration window has two panes, the left pane displays the configuration sections and the right pane displays the parameters of the selected section.

Before using the configuration tool, a connection to the server must be established. When a connection is established, the Connect button will be disabled and the Disconnect button will be enabled. The right pane will be populated with the parameters of the selected section.

When connected, the main configuration window appears as follows:

- · **Send Logoff Message:** Sends a logoff request will to the server. The server will end the session normally.
- · **Force Logoff:** Sends a logoff message to the server, ending the session immediately.
- · **Restart:** Restarts the server instantly. The configuration tool will be disconnected from the server. When a Map Server is defined, and more than one instance of Viz World Server is defined, all instances will be restarted.

> ⚠ **Note:** Most configuration changes requires a server restart before they take effect.

> ⚠ **Caution:** When Viz Maps Server Config tool is running the server is locked. No client connection will be accepted.

To connect to the server

- Enter the server name or IP address in the Map Server field, and click Connect.

7.1.2   Template

- **Project Template:** Defines the default project that will be used by the server when initially asking for a map or the client requests a project that does not exist.

7.1.3   Locations

The Locations section defines the path to required software components.

- **Root:** Defines the installation folder.
- **Licenses:** Defines the license file(s) folder.
- **Settings:** Defines the path to the settings folder.

7.1.4   Logins

The *Logins > Users* section displays the users configured on the server. Viz World Clients use the pre-defined Guest user to log on to the server.

The *Logins > Guest* screen is used to set some of the guest user permissions.

> ⚠ **Note:** Users are added and removed from Viz World Classic only.

- **Allow <user name>**: Allows the user to connect to the server when running WME or Viz.
- **Allow <user name> Projects:** Allows the user to access projects defined in the <user name> Project Folder.
- **<user name> Project Folder**: Defines the path to a folder containing the user's projects.

7.1.5   License

The License section displays information about the current server license and enables the user to load other license files.

> ⚠ **Note:** If the license is not valid, the server will not start.

- **Add License From File:** Opens a file browser that enables the user to load additional license features from a different license file and to add it to the system. After a new license file is added, the Apply button is enabled.
- **Dump License Info:** Saves the license information, that is displayed in the text box, to a file.
- **Apply:** Applies the new license information to the system's license file.

### To manually add a license file

Locate the License file (*.lic), copy and paste it into the *Licenses* folder:

- **32 bit**: `C:\ProgramData\Curious Software\Curious World Maps\Licenses`
- **64 bit**: `C:\ProgramData\vizrt\Viz World\Licenses`

To add a license file using the Maps Server Configuration tool

1. Start the server configuration tool.
2. Select the License section.
3. Click the **Add License From File ...** button.
4. Locate and select the file and click **Open** to add the new license file.
    - The license becomes visible in the Edit License window.
5. Click **Restart** to start the server with the new license.

To add a license file using Viz World Classic

When starting Viz World Classic without a license, a window appears informing that a valid license cannot be found.

1. Start the Viz World Classic application
2. Click the **License** button to open the Software License window
3. Click the **Edit License File ...** button to open the Edit License window
4. Click the Add License from a File ... button to browse for the License file (*.lic)
5. Select the License file and click Open
    - The license becomes visible in the Edit License window
6. Click **OK** to save the License. The license is saved to the License folder
7. Exit the application and run the Viz World Server.

7.1.6 Maps

The Maps section is used to define the following general map settings:

- - Database
  - Database Features
  - Disputed Regions
  - Default Projection

- Map Legend
- Locations
- User DEMs
- Attribution
- To position the attribution image
- Bing
- Digital Globe
- Proxy Settings
- Display
- Street Admin
- Imported Data
- Plugins
- Place Finder

Database

- Database: Select the data base type. It only displays location entries that are visible in the map area.
- Shared User Map Data: Defines the source of data used by the database.

Copyright © 2019 Vizrt   Page 28

Database Features

- · Accented characters: Handles accent characters in labels such as ~ in España.
- · DataBase Features: Defines whether the WME search tool will use additional databases in the system or only the Viz World database.

Disputed Regions


- · Region: Displays a list of the disputed regions defined in the system. Select one of the disputed regions to be configured.
- · Configuration: Displays a list of region and border options related to the selected disputed region in the Region parameter. Select an option from the list and the graphic display will change according to the selected option.

Default Projection

Sets the default projection for when a client opens a template that does not have a map layer. The following options can be set:

- **Globe:** Sets a globe projection.
- **Cylindrical Equidistant:** Sets an unprojected map. Longitude and latitude are mapped directly into X and Y coordinates.
- **Miller Equidistant (37 30):** Relative distances are correct. Angles are correct around 37 degrees 30 minutes North.
- **Miller Equidistant (43):** Relative distances are correct. Angles are correct around 43 degrees North. Minimum scale distortion over continents.
- **Miller Equidistant (50 28):** Relative distances are correct. Angles are correct around 50 degrees 28 minutes North.
- **Gall Isographic:** Relative distances are correct. Angles are correct around 45 North.
- **Lambert Cylindrical Equal Area:** A cylindrical equal area projection which uses the equator as the parallel of no distortion.
- **Behrman Cylindrical Equal Area:** A cylindrical equal area projection which uses 30 degrees North as the parallel of no distortion.
- **Tristan Edwards:** A cylindrical equal area projection which uses 37 degrees 38.3 minutes North as the parallel of no distortion.
- **Peters**: De-emphasizes area exaggeration in high latitudes.
- **Gall Orthographic:** A cylindrical equal area projection which uses 45 degrees North as the parallel of no distortion.
- **Balthasart Cylindrical projection:** An orthographic projection onto a cylinder secant at the 50 degrees parallels. It is cylindrical equal area, but distortion of shape increases with distance from the standard parallels. Scale is true along the standard parallels and constant between two parallels equidistant from the equator. This projection is not equidistant.
- **Mercator:** Mercator projection. Scale and angles correct only at the equator. Very distorted at the poles.
- **Miller:** Distances and angles are only correct on the equator. Shapes and areas are distorted, especially at the poles - but less than with Mercator.
- **Albers Equal Area Conical:** A conical projection which is useful for maps which are wider than they are high, such as the continental United States.

- **Stereographic, Polar Stereographic (North and South):** A projection which has minimal distortion at the center of the map. Most useful for maps that are zoomed to show whole countries.
- **Transverse Mercator:** A projection which has minimal distortion at the center of the map. Most useful for maps that are zoomed to show whole countries.

Map Legend


Sets the default unit titles for map legends.

Locations

The Locations parameters define the path to folders containing relevant data for the specified parameters.

The **Natural Earth** option can be used to add, remove and color correct global and/or local CMR (Curious Multi Resolution) imagery. Global imagery is what is typically used as base maps, whereas local imagery are more detailed imagery of local places (e.g. coastal areas and cities).

See Also

- Open Street Map Downloader

User DEMs

The User DEMs (Digital Elevation Model) define the path to a folder containing elevation data.

Attribution

Defines where the attribution should be placed on the screen.

- **Attribution image (gray rectangle):** Sets the location of the attribution image on screen.
- **Output Attribution Font:** Sets the font used for the on screen credit.

To position the attribution image

- Drag the gray rectangle that represents the attribution image area to the desired position.

Bing

Bing Maps Platform (previously known as Virtual Earth) is a set of images (satellite and others) stored on Microsoft's Bing Maps Platform servers. The images can be used by Viz World Classic, but requires a credit mark (Attribution image) to be displayed on screen.

- **Bing Cache:** Defines a cache folder for the images retrieved from the Bing Maps Platform server.
- **Empty Cache:** Deletes all files from the cache folder.
- **Bing Connection:** Allows you to test that the Bing Maps Platform server is online.

  > ⚠ **Note:** Microsoft Bing requires an internet connection and will not work without a license.

Digital Globe

- **Digital Globe cache**: Sets the location of the digital globe cache. For reference, see the Bing section.
- **Digital Globe URL**: Set the URL of Digital Globe, allowing you to configure new parameters if Digital Globe's API changes.
- **First Look URL**: Sets the URL of First Look (deprecated)

> ⚠ **Note:** Digital Globe requires an internet connection and a license. If used without a license a watermark will appear.

- **Empty Cache:** Clears the cache
- **Cache location**: Sets the location of the Google Maps cache. For reference, see the Bing section.
- **Test Google Maps Connection:** Tests the connection

> ⚠ **Note:** Google Maps requires an internet connection and a license.

Proxy Settings

The Viz World Server should be allowed to access the following servers:

- http://www.digitalglobe.com
- https://services.digitalglobe.com

Display

- **Alternate Label Display:** Sets a custom language and defines the labels' source priority, effecting the list of label options displayed to the user. For creating multi-language files and using them see the Map Name Editor and the Using the Map Name Editor sections.
- **Street Data:** Defines the visual properties of street edges when drawn on the maps.
- **Auto Feature Preview:** Defines what features will be previewed in Viz World's Map Editor (WME) when pressing the auto features button.
- **More Label Setting:**
    - **Automatically scale map labels**: When this option is checked, changing the size of a project or TPL label styles will also scale the labels proportionally. **Note**: This only applies to label styles created in Viz World Classic and used with the Map Editor Classic.
    - **Prefer Region Capital Label**: When turned ON the auto-features will force the type of feature to "Region Capital" instead of based on the feature size (e.g. Town 1K, Town 1M) which is the default
- **Fit Map by Width**.

See Also

- Map Name Editor
- Using the Map Name Editor
- Maps Configuration

Street Admin

The Street Admin section is used to display information about the loaded roads data in the system and road data licensing information.

Re-Scan: When pressed, the configuration tool will check the loaded street data and refresh the display.

Imported Data

Allows you to add shape files (shapes, lines, names and so on) which later can be imported to Viz Artist through the Map Editor (WME) and added to your map.

Plugins

A list of plugins that are used for searching the web (not the Viz World database).

Place Finder

Viz World Server allows receiving maps of locations/features, same as the Place Finder plugin. This can be used by Escenic or any other web application, or for demonstrations of Viz World. For more information, see the Place Finder section.

7.1.7 Standalone Clients

A standalone client is an application running WME on machines without a Viz installation.

- · **Export Folder:** Defines the save path for standalone client applications.

- · **Export Formats:** Image formats are presented to users when saving images. Add a format for each combination of file format and compression options you wish to use. The Options button allows you to set color (black and white, grayscale, 256 colors etc.), and filter

options.

7.1.8 Symbols

Symbols are created and exported from Viz World Classic, and can be imported using the server configuration tool such that client users can add them to their maps.

See Also

- Symbols Tab

7.1.9 Timeouts

This section is used to set server timeout values.

- **User Timeouts:** Sets the timeout values for clients logged onto the server:
    - **Minutes Inactivity (Plugins):** Sets the timeout for client connections when the WME is opened through the CMWClient plugin. If no map requests are sent to the server during the period of time (in minutes) specified in this parameter, the server will disconnect the client.
    - **Minutes Inactivity (Interactive Navigator):** Sets the timeout for client connections when an interactive Navigator scene is used. If no map requests are sent to the server during the period of time (in minutes) specified in this parameter, the server will disconnect the client.
- **Periodic Restart:** Enables automatic restarts of the server. It is mainly targeted at 24/7 stations, where Viz Engines are up and constantly requesting maps. The Automatic restart enables the server to restart at the specified time or after a defined period of time, disconnecting all clients and clearing used memory. This is important when the server is used heavily and a lot of maps are generated.
    - **Restart server periodically:** Sets the server to restart periodically based on the After or At Time parameters.
    - **After:** Sets the amount of time (hours) for how long the servers should be running before the server should be automatically restarted.
    - **At Time:** Sets the time for when the server should be restarted.

7.1.10 Proxy Server

This section is used to define the proxy server connection settings. Viz World Server will connect to the internet to fetch data from Bing Maps Platform or Imagery on Demand servers. If the system uses a Proxy Server that requires authentication, this page is used to provide the login details for the Proxy Server.

- **Name:** Sets the user name.
- **Password:** Sets the user password.

See Also

- Bing
- Digital Globe
- Google Maps

7.1.11 Server Logging

This section defines whether or not the server will log system messages to a log file.

7.2 Viz Engine/Artist Configuration

This section contains information on how to configure the Viz Artist render engine.

7.2.1   Maps Configuration

- **Map Server:** Enables or disables Viz World Server (WoS) connection for Viz World Client (WoC).
- **Server:** Sets the Viz World Server host.

> ⚠ **Note:** If a Server Allocator is used, it should point to this location.

- **Project:** Sets the default map project that will be opened with the client application.
- **Available:** Lists all available Viz World Server projects.
- **Map size:** Sets the default map size that will be used with the client application.
- **Cache:** Enables caching of maps for faster preview and fetching of maps. Especially useful for journalists and operators using Newsroom Component and Viz Trio respectively.
- **Cache Directory:** Sets the cache directory for cached maps which can be a local drive, mapped drive or a Universal Naming Convention (UNC) path.

> ⚠ **IMPORTANT!** Make sure the Cache Directory folder is configured with read and write access rights.

- **Memory (Images):** Sets the number of images to keep in memory.
- **On disk (Days):** Sets the number of days to save images on disk.
- **2nd Cache Directory**: Enables a second cache (see Cache above). The main purpose of the second cache is to enable redundancy in those cases where a main cache directory is on a different computer and for some reason fails. Another use case is to use it as a local cache to save loading time (e.g. if you load all borders for the entire world you would have 100MB+

of cached files). In order to shorten load time you can copy large static files to the correct local cache folder. In the 3D Map Setting plugin you will also find a *Sync Local Cache Folder* button which will copy all the needed files to your local cache. Note that the second cache directory settings can only be used by Viz World version 12.0 and later.

· **Priority**: Sets the machine's connection priority to the Viz World Server (WoS). Setting a number, where 1 is the lowest and 100 is the highest you may override connection priorities set by other machines. The configuration interface will allow you to prioritize client connections from Viz Artist and On Air Viz Engine's used for preview and program output. Viz Engines must be in On Air mode for them to be prioritized. For Viz World's Map Editor you can set it from the Context Menu. To enable this behavior on the server side you need to enable WoS to prioritize its connections/logins. If the configuration option is not visible, please read how To add the VizWorld.ini file and set the priority.

· **Network Monitor**: Enables you to monitor relevant network connections (server and cache folders). If you do not monitor the network and you try to connect over a "disconnected network", connecting to a server or a UNC path, it will take time before the system reports back (e.g. 30 seconds or more). Enabling network monitoring will avoid such connection issues. Note that the network monitor will only monitor a cache folder that use a UNC path (not mounted/mapped drives). If the configuration option is not visible, please read how To add the VizWorld.ini file.

· **Languages:** Sets the current language to be used on labels fetched from Viz World Server. For more information, see the Display section.

· **Attributions:** Adds an attribution to the map. Alternatives are; Static and Dynamic.
  · **Dynamic:** Displays the attribution when a licensed imagery is in view and disappears when the image is out of view.
  · **Static:** Displays the attribution as long as there is a licensed imagery in the scene.

· **Attribution Font:** Sets the font for the attribution.

· **Bold:** Sets the attribution font to **bold**.

· **Italic:** Sets the attribution font to *italic*.

· **On Top:** Places the attribution image to the top in the screen. Default is bottom.

· **On Right:** Places the attribution image to the right in the screen. Default is left.

7.2.2 To add the VizWorld.ini file

1. Create a and save a VizWorld.ini file to the following location:
   `C:\ProgramData\vizrt\viz3\Maps`
2. Open the file and enter the following:

```
Monitor=1
Priority=1
Language=[my Language ID]
```

3. Save the file and start e.g. Viz Config to see the configurable parameters

`Monitor` enables network monitoring. See the **Network Monitor** setting, listed above.

`Priority` sets Viz' connection priority to the Viz World Server. See the **Priority** setting listed above, and the Server Launcher Configuration section on how to enable prioritized connections on the server side.

`my Language ID` refers to the order of languages in your list of languages (e.g. English = 0, Arabic = 1, Hebrew = 2 and so on). See the **Languages** setting, listed above.

7.3 Cache Configuration

When working with Viz World in a server/client environment, a cache is used to reduce the load time of scenes in Viz. The cache is a shared network storage folder, common to all Viz Engines in the system. The cache is managed by the Viz Engine machines.

> ⚠ **Note:** In complex environments, Viz Engine machines can be grouped so a different cache is defined for each group.

This section contains information on the following topics:

- Map data flow
- Cache Location
- Defining the Cache
- Cache Folder Structure
- Caching - Viz Trio
- Caching - Viz Pilot

7.3.1 Map data flow

The maps data stored in the cache is produced by the Viz Engine machines, running World Map Editor applications. When WoC is launched, it connects to the server and enables the user to select a map and add information to the map. When the user accepts the selected map (by pressing the OK button in the maps editor (WME)), the map information will be sent to the scene (and to the relevant WoC plugins used in the scene) from the server. WoC plugins will load the received data and then store it in the cache. Now, when a scene is initialized, the WoC plugins will look for the data in the cache and load it, without connecting to the server.

Since the most time-consuming task in this process is generating the maps, using the cache reduces that time to a minimum and the maps are generated only once.

> ⚠ **Note:** Before setting a cache folder in a server/client environment, a shared network drive, mapped on all Viz Engine client machines should be created. The cache folder is defined on the shared drive, so all machines will have access to the cache.

7.3.2 Cache Location

The following are some simple guidelines that will ensure caching is optimized when using one or several Viz Engines.

- **One:** Set the cache location local to that renderer.

· **Two or more:** Set the cache location to the map server (or other shared network drive) so that one renderer is not favored over others.

7.3.3   Defining the Cache

The client cache is defined using Viz Engine's configuration tool (Viz Config). When configuring the cache environment make sure that the following parameters are identical on all Viz machines:

· Cache Directory
· On Disk (Days)

> ⚠ **Tip:** Control clients should have their cache location(s) set to the same location as defined by the Viz Engine(s).

To configure the cache directory

1. Start **Viz Config** or open the configuration interface by clicking the **Config** button on the main menu in Viz Artist
2. Select the **Maps** section
3. Set the **Cache Directory** to the defined shared network drive and the folder used as the cache's main folder

> ⚠ **Note:** The Cache Directory has to be identical on all Viz Engines that share the cache. UNC paths are also supported.

4. Set the **Memory (Images)** to the required value (default is 32). This parameter defines the maximum number of map images stored in Viz memory when initializing a playlist

> ⚠ **IMPORTANT!** Set the number of images to zero (or a low value) on control machines used in the system. The control machines are inferior to Viz Engine machines and it makes no sense to load a large number of images when it is only used for preview.

5. Set the **On Disk (days)** parameter to the maximum number of days that the images will be stored in the cache. When Viz is launched, it will clean the cached map images that are older than the value defined in the On Disk (days) parameter
6. Click **Save**

To configure the 2nd cache directory

1. Start **Viz Config** or open the configuration interface by clicking the **Config** button on the main menu in Viz Artist
2. Select the **Maps** section
3. Set the **2nd Cache Directory** to your local computer or a defined shared network drive and the folder used as the cache's main folder

4. *Optional*: Enable network monitoring
5. Click **Save**

See Also

- [Viz Engine/Artist Configuration](#)

7.3.4 Cache Folder Structure

When using cache in a client/server configuration, WoC plugins will manage the cache and sort generated data in several folders under the cache folder. The cache folder hierarchy is created automatically. Only the cache root directory is configured in Viz. The defined cache folder for all clients is the root cache folder. Under the root cache folder, a version sub folder is created using the WoC plugins version. Under each version folder, several sub folders are created, according to the requested data:

- **3DLine-Cache:** Stores lines from the WME as OpenGL vertices.
- **3DBorder-Plugin-Cache:** Stores selected borders based on the Region-Cache data.
- **3DRegion-Plugin-Cache:** Stores selected regions based on the Region-Cache data.
- **AtlasCacheFolder:** Stores Downloaded images from Microsoft to enable a smooth animation and faster response time during navigation. Images are stored under sub-folders according to the texture compression used.
- **BorderManagerFullWorld-Cache:** Stores unselected borders based on the Region-Cache data.
- **CWMClient-Cache:** Stores map images and label information that is reused by Viz when loading the scene.
- **Region-Cache**: Stores region vector data.
- **Street-Cache:** Stores street vector data.
- **StreetManager-Cache:** Stores unselected streets based on the Street-Cache data.

> ⚠ **Note:** The 3DBorder, 3Dregion and BorderManagerFullWorld cache is based on Region-Cache data after a projection is set, and converted to an OpenGL format.

> ⚠ **Example:** The country Norway will only have one cache file under Region-Cache (since there is only one Norway), but could have many under other folders with different projections.

General Caching Rules

The CWMClient-Cache folder is cleaned when Viz is launched (any of the Viz Engines using the cache), according to the On Disk parameter value.

The data in the cache folders (except for the CWMClient cache) are not deleted when cleaning the cache since it does not change and it can be reused all the time.

See Also

- [To configure the cache directory](#)

7.3.5 Caching – Viz Trio

This section describes Viz Trio specific commands/actions that influence how map data is cached when Loading pages, Initializing all pages and performing a Direct Take.

> ⚠ **IMPORTANT!** Set the same cache directory for the local Viz, and program and preview channels.

Loading pages

Opening a scene for preview generates all cache files needed for the scene in the file cache. Any change to the page through Viz Trio (CWM location, hop locations, labels, selected regions and so on), immediately generates all required cache files. When pressing *Take*, Viz Engine will load to memory all needed map cacheable elements through the file cache that the preview machine just generated without the need to connect to the map server.

> ⚠ **Note:** Applies only if both of them have same cache folder.

Initializing all pages

The **Initialize All** button/command will load all scenes to memory (program & preview renderers). All necessary map data will be loaded from the cache files.

> ⚠ **Note:** It is assumed that each page has been loaded in preview once before, and that cache files have been created.

Direct Take

The **Direct Take** button/command will immediately load the scene into Viz Engine. All necessary map data will be loaded from the cache files that the preview has generated once.

> ⚠ **Note:** It is assumed that each page has been loaded in preview once before, and that cache files have been created.

See Also

- To configure the cache directory

7.3.6 Caching – Viz Pilot

Caching of map data can be achieved by running Viz Pilot's Thumbnail Generator on the same machine as your Viz Engine.

See the *Viz Pilot User Guide* on how to setup and configure the Thumbnail Generator.

When running Viz Pilot in a non-preview configuration, any change to any map element that requires caching will **not** create cache files. This will result in longer loading time of the Viz Engine

because data maps, labels and polygon data has to be requested from the map server. It is important to request at least a single image preview, such that cache files will be created.

> ⚠ **IMPORTANT!** If you are running a local Viz, set the same cache directory for the local Viz as for the program and preview channels.

See Also

- To configure the cache directory

8 Server Operation

This section describes how to start Viz World Server (WoS) and how to use the Server Launcher to start, stop and configure the WoS and Server Allocator.

This section contains information on the following topics:

- Starting Viz World Server
- Server Launcher
- Using Server Launcher
- Server Launcher Configuration
- Server Allocator Configuration

8.1 Starting Viz World Server

8.1.1 To start the Server

1. Double-click the desktop shortcut, or
2. Select the program from the Start menu.
   - All Programs > Vizrt> Viz World Server

A console window appears that loads the database. When done, the server is ready to receive requests from clients.

8.2 Server Launcher

Viz World's Server Launcher is a tool used to start, stop and configure the Viz World Server and Server Allocator. In addition, it will also start a process that generates thumbnails of map templates used by the Viz World Client's Map Designer tool.

8.3 Using Server Launcher

The Server Launcher is an application installed as part of the Viz World Server, and can be found on the programs menu. The Server Launcher is run as a service by default.

When the Server Launcher is configured, the Server Allocator distributes client requests between the registered servers and server machines, balancing server loads and the number of client requests. When configured in a complex environment, multiple map servers with multiple Server Allocators can be used to allow full redundancy and optimal resource distribution.

Starting a single instance of the maps server can be done from the program menu or by using the desktop icon.

Starting the Server Allocator, in order to setup a redundant system and/or configure more than one instance of the map server on one server, is done using the Server Launcher.

When the Server Launcher is running it will typically be floating on top of the desktop; however, it can be minimized to the tray.

8.3.1   Desktop Icon

The status of the Server Launcher is indicated by the color of the icon:

- Normal icon + green led = Licensed, running
- Normal icon + grey led = Licensed, not running
- Greyed icon + green led = Not Licensed, running (this only applied to Service Allocator, since it is not licensed)
- Greyed icon + grey led = Not Licensed, not running

8.3.2   Tray Icon

The tray icon allows you to minimize the application to the tray and restore it.

- **Restore / Minimize To Tray:** Restores or minimizes the Server Launcher from or to tray.
- **Start / Stop Server:** Starts and Stops the Server Allocators and the Viz World Server without exiting the Server Launcher application.
- **Options:** Opens the Options window for configuring the number of Viz World servers and Server Allocators. See Server Launcher Configuration for more information.
- **Exit Launcher:** Closes the Server Launcher application. Server Allocator and Viz World server will still be running.
- **Exit & Shutdown (Not Recommended):** Closes the Server Launcher application. Stops all Server Allocator services and the Viz World server.

8.4 Server Launcher Configuration

Viz World Server is configured using the Server Launcher.

Click the Server Launcher's Options button in order to configure the map server.

- **Preferences:** Allows the user to set the local server count and enable the Server Allocator.
  - **Local Server Count:** Defines the number of server instances that will run on the machine simultaneously. Default value is 1. When setting the number of instances for each machine, machine hardware should be considered. Every server instance requires physical memory (RAM) and makes intense use of the CPU. Do not abuse this parameter, since client and server performance will be affected.
  - **Enable Priority Login**: Enables Viz World Server to prioritize its inbound client connections. Viz' configuration interface will allow you to prioritize client connections from Viz Artist and On Air Viz Engine's used for preview and program output. Viz Engines must be in On Air mode for them to be prioritized. For the Map Editor you can set it from the Context Menu. For more information on how to set priorities see the Maps Configuration section.
  - **Run Server Allocator:** When disabled (not selected), the Server Allocator will not run on the machine. When enabled (selected), the Server Allocator will run and use the parameters defined in the Server Launcher's Options window. Default mode is disabled. Server Allocator does not require any license and can be run on any machine.

    > ◆ **Important!**
    > If the Server Allocator is enabled, even for just one machine, the machine must be defined in the Controlled WoS list.

- **Launch Options:** Allows the user to run Viz World Server and the Server Launcher as a service, or in console mode. If run as a service, the system can automatically start all server instances when the machine starts without the need to login. If run in console mode, all instances must be manually started.

- **Controlled WoS:** When enabled (see Run Server Allocator), the Controlled WoS settings allows the user to configure the controlled WoS instances.
    - **Machine:** Sets the name of a machine running Viz World Server.
    - **Count:** Sets the number of instances running on the machine. Default is 1.
    - **Priority:** Sets the machine's priority. If more than one machine is defined, the priority must be set for each machine.
    - **Instances:** Sets the number of instances that are controlled by the machine. If the machine has more than one instance running, it is possible to open the Instance Control (click Set) To set the controlled instances.

> ⚠ **Note:**
> When the Server Allocator allocates a server to a client, it will pass this name to the client, hence, its hostname/IP address must be accessible to all clients.

8.4.1   Setting Priorities

Normally all servers will use the same priority (1). In more complex scenarios a lower priority can be used, for example when two servers are running two instances each and an allocator.

One server is typically dedicated to an On Air engine and another to a Viz Artist (designer) client such that a designer client will not steal a token from an On Air engine.

Example setup:

- Map server A is for the On Air engine and it controls two instances on map server A with priority 1, and two instances on map server B with priority 2.
- Map server B is for the Viz Artist designer and it controls two instances on map server B with priority 1, and two instances on map server A with priority 2.
  The Server Allocator will not redirect any clients with map server A as default to map server B if it can give them an instance on map server A because map server B has a lower priority. So, only if the instances on A are out of license tokens, or not responding, the Server Allocator will direct clients to map server B. And the same for B.

Another example is in a scenario where there are two allocators (one in Location 1 and another in Location 2), all clients from Location 1 should be connected to the server in Location 1, and all clients from Location 2 should be connected to the server in Location 2, and only if anything goes wrong should clients be allowed to connect from Location 1 to Location 2.

8.4.2   Configuring the Server

8.4.3   To add or remove instances

- Click the **+** or **-** buttons in the Options window to add or remove instances.

8.4.4   To set the controlled instances

1. Click the **Set** button in the Server Launcher's Options window.
2. **Double-click** the instance to set the control mode to **Controlled** or **Not Controlled**.
3. Click **OK**.

> ⚠ **Note:**
> The number of controlled instances is displayed in the Instances field and column seen in the Options window,

8.5   Server Allocator Configuration

Optimal usage of system resources can be obtained by using multiple map servers, running multiple map servers on each machine, with a Server Launcher launched on each of the machines.

The system can be configured with:

- one allocator for multiple map servers,
- one allocator on one machine with multiple servers, or
- multiple allocators with multiple server machines.

8.5.1   Single Server Allocator Configuration

The simple environment setup is when running one map server with multiple map server instances and a Server Operation. In this configuration, the Server Allocator will accept client requests and divert them to the server instances on the same machine. Client connections will be equally divided between the map server instances, allowing better response time and load balancing of server processes.

8.5.2   Multiple Server Allocator Configuration: Classic Redundancy

Having multiple servers, where in each there is a Server Allocator running that controls all WoS instances of all machines.

This configuration guarantees most redundancy as each Server Allocator is updated with the current status of all WoS servers, and in case of a failure in one of the machines, other Server Allocators can provide redirection to any available WoS.

The maximum number of server instances that can be run per machine is 4. Each server instance should have 4GB of memory and 2 CPUs. So on a machine with 4 dual CPUs and 16 GB of memory you can run the maximum of 4 server instances.

The above diagram describes a system with two machines running a Server Allocator and **four** map server instances on each machine. If the client is configured with both machine names, full redundancy within the system will be accomplished.

> ⚠ **Note:** Any configuration combination between the Server Allocators and the map server instances is valid.

See Also

· [Server System Requirements](#)

9 World Map Editor

The World Map Editor (WME) is a component of the Viz World Client. WME allows you to browse and select map features, similar to those created using Map Editor Classic. In comparison with Map Editor Classic, Map Editor offers almost the same features, which allow you to create stunning maps in no time.

This chapter contains information on the following topics:

- · Getting Started
- · Tools
- · World Map Editor Shortcuts

9.1 Getting Started With Map Editor

Once you have the Viz World Client installed you can start the Map Editor and connect to the Viz World Server. Once connected you will be able to open existing design projects.

9.1.1 To start the Map Editor

Normally the Map Editor will be launched from Viz Trio, Viz Artist or Viz Pilot.

9.1.2   To connect to Viz World Server

> ⚠ **Note:** When the Map Editor is launched from a Vizrt application (e.g. Trio, Artist, Pilot), it will automatically connect to the server that has been configured within that application, rather than the server configured within the Map Editor.

1. Start the Map Editor
2. Click the Settings button ⚒
3. Set the Viz World **Server** hostname. If not specified, the Map Editor will connect to `localhost`.
4. Click Save

9.2   Tools

This section contains information on the following topics:

- Map Editor Toolbar
- Settings
- Search
- Layers
- Extra Data Manager
- Details
- Shapes Tool
- Streets Tool
- Show or Hide Map Features
- Quick Map
- Locator and Preview
- Preset Editor
- Multihop Editor

9.2.1   Map Editor Toolbar

The Map Editor has the following toolbars:

- Horizontal Toolbar
- Vertical Toolbar
- Quick Map Toolbar
- Locator and Preview Tabs

Horizontal Toolbar

The horizontal toolbar contains the following options:

- ⊡ **Save Favorites**: Save current project as a favorite project. Unlike projects which only contain the base map styling, a Favorite is a project which also has data saved as part of it, such as selected countries, loaded streets, and labels.

> ⚠ **Note:** User favorites will not be synchronized across servers when working with server allocator. When working with multiple servers, synchronizing user favorites can be done as an automated process of replicating the relevant folders. User favorites are stored by default under C:\Program Files\Vizrt\Viz World\Users\Default\Favorites.

- ⊡ **Open Favorite**: Open a favorite project.
- ⊡ **Open Project**: Open existing map template files.
- ↺ **Undo**: Undo last change
- ↻ **Redo**: Redo last change
- ⊡▾ **Copy Map to Clipboard:**
    - Click the icon to copy the current map view, and its details, to a clipboard that can be used later on when reopening World Map Editor.
    - Select a previously copied map from the dropdown. The clipboard is a local list, for the currently active directory.
    - Delete an item from the clipboard list by right clicking an item and selecting Delete from the context menu.
- **Search**: Search the map.
- **Select stylesheet**: Select one of the template's available stylesheets.
  If the stylesheet uses either *Digital Globe* or *Microsoft Bing*, an additional dropdown will allow you to select the profile of imagery to use from the provider. The different Profiles provide a different imagery set for the same location.

> ⚠ **Note:+Vivid** provides a set of seamless tiles of imagery for every level, however some images may not be the most recent imagery. The +Vivid option on Digital Globe is a paid subscription, contact your local Vizrt Sales representative if you require a license.

- ⊡ **Notifications**: Displays notifications of errors.
- ⊡ **Settings**: Change the Settings (Viz World Server, Language, Map Legend, Safe Guide)
- ⊡ **Information**: Displays version information about the Viz World Client and Server.

Vertical Toolbar

The vertical toolbar contains the following options:

- **Layers**: Enables you to search for and filter features based on the current map Layers in view.
- **Details**: Shows the Details for all selected features. *Right-clicking* the button will open a context menu that allows you to *fit to*, *center to* or *clear all details*.
- **Pan:** Enables the user to click and drag on the map to move the map in the direction of the drag.
- **Zoom:** Zooms the map according to the area selected. To select an area, click and drag to draw a rectangle.
- **Shapes tool**: Opens the Shapes Tool. *Right-clicking* the button will open a context menu that allows you to select the shape.
- **Streets tool**: Opens the Streets Tool.
- **Inverse Colors**: Toggle the color of the map legend and map features (countries, cities, etc.) See Settings for how to enable/disable the map legend.
- **Show/Hide Features on Map**: Click the button to show or hide the selected map features. Click the arrow to select which map features to show. See Show or Hide Map Features.

Quick Map Toolbar

Use this to access the Quick Map features.

Locator and Preview Tabs

Use this to access the Locator and Preview features.

9.2.2 Settings

- **Server:** Set the Viz World Server hostname. If not specified, the Map Editor will connect to `localhost`.
- **Language**: Select from the available map languages. See Map Name Editor for information on how to configure the languages.
- **Map Legend:** Enable or disable the map legend.
- **Safe Guide:** Enable or disable a safety area around the map (e.g. for text safety)

9.2.3 Search

The search option allows you to search for, and add notable locations to the map. The map can then be fitted, or centered around these locations.

From the results list, each item has the options:

- / : **Add/remove** the selected location to/from the map
- : **Fit** the map to the selected location
- : **Center** current map view to the selected location
  All locations that have been added to the map can also be edited from the Details view.

9.2.4   Layers

Places

Enables you to search for and filter features based on the current map layer in view. You can also sort based on Country, Name, and Type.

Streets

This tab allows users to load street data by clicking **Select Streets to Load**, and using the Extra Data Manager, as well as add items to the map using the Extra Data Browser.

The roads in the visible map can be loaded into the list by clicking **Load Visible Streets**.

Shapefile

This tab is to allow users to load Extra data such as Shape files.

KML

The KML Manager lets you load Keyhole Markup Language (KML) files which can then be added to the map. The KML file can be uploaded from the Viz World Server or opened from a local file.

- **Load:** *Load* a file from the Viz World Server. Clicking the **Load** button, opens the KML Browser and lists all the available KML files. It works the same way as the Extra Data Browser.
- **Open:** *Open* a file from the file system, but do not copy it to the Viz World Server
- **Upload File**: *Open* a file from the file system and *copy* to the Viz World Server

> ⚠ **Note:** If the KML file includes a camera position, then the map will zoom to that position, otherwise the map will focus on all of the data found in the file.

KML files can also be manually imported into the server, and must be placed in the following folders:

- 32 bit:
    - `C:\ProgramData\Curious Software\Curious World Maps\KML`
    - `C:\ProgramData\Curious Software\Curious World Maps\Users\Default\KML`
- 64 bit:
    - `C:\ProgramData\vizrt\Viz World\KML`
    - `C:\ProgramData\vizrt\Viz World\Users\Default\KML`
        Any files uploaded from the client will be stored in this same location.

First Look

The events tab is a feed of events from Digital Globe's FirstLook service.

FirstLook provides rapid imagery of major global events, such as:

- Natural disasters: Earthquakes, fires, tornados, hurricanes
- Man-made crisis: Terrorism, large accidents
- Political instability: Riots, civil war
- Human interest: World Cup, Olympics, F1, NFL

It requires a yearly license to use the imagery.

9.2.5 Extra Data Manager

The Extra Data Manager is available from the Layers Tool and allows users to manage extra data that is stored on the Viz World Server.

> ⚠ **Note:** In order to work with Extra Data, the Viz World Server must have data loaded.

> ⚠ **Note:** Streets data requires additional license features and the installation of street data on the server.

Using Extra Data

1. In the Layers tool, click on the Streets tab, to open the Extra Data Browser. (this will be empty if no data has been selected).

2. Click on **Load Streets** to open the Extra Data Manger.

3. Navigate to the required data and use the Add, Fit and Centre buttons to select the data and/or move the map.
   Close the Extra Data Manager when finished.
4. Open the Extra Data Browser again to see all the loaded data and add features which are related to the loaded data.
5. Data can be deselected either from within the Extra Data Manager or the Extra Data Browser, using the 'X' button.

Extra Data Manager

In the Extra Data Manager, the view can be switched between Flat List view and Tree view, using the buttons at the bottom of the window.

The **Flat List view** presents the data in a flat structure with a navigation bar at the top. To navigate in the data, double-click an item in the list to open it, or use the drop-down menus. In this case, the Filter only filters the content of the current directory.

The **Tree view** presents the data in a hierarchical structure. To navigate in the data, double-click an item in the list. The Filter filters the whole tree and lets you navigate within the results using Enter and Shift+Enter keys or the '^' and 'v' buttons.

Extra Data Browser

The Extra Data Browser displays all the loaded data and can be used to add features which are related to the loaded data.

9.2.6 Details

The Details view allows you to edit the name and appearance of details. Changes can be made to multiple details by selecting them together. The details in the list can be reordered by dragging them, or easily hidden from the map.

Custom styles and style families can be created in the Map Designer using the Style Editor. These styles will then be available in the Editor.

The **icon** used for each detail can be changed by selecting the detail in the list and browsing for a new icon in the list of icons.

Details can be **sorted** alphabetically using the ▲ ▼ buttons.

Show/hide each detail, without removing it from the list, by clicking the 👁 🚫 icon. When a detail is hidden, it is not rendered in the scene.

Clicking the Edit button next to each item in the Details list allows editing the following features:

· **All Caps**: Caps on or off
· **Add to Database**: New name alternatives (e.g. language specific) can be saved to the database
· **Label Location**: Adjust the location of the detail's label.

The context menu provides the following options:

· **Fit to details**: Fits the map according to the selected details
· **Center to details**: Centers the current view according to the selected details
· **Remove details**: Removes all selected details
· **Clear all details**: Removes all details regardless of selection

> ⚠ **Note:** If the default style defined in the server is not available in the scene designs, then the first design which is available in that scene will be used.

9.2.7   Shapes Tool

The Shape Tool lets users draw shapes on the map.

Context Menu

A right-click or a long left-click on the Shapes Tool icon will present a context menu with the following options:

· **Spline Shape**: Draw segments of a smoothed, curved line. It can be closed or open. Double click to finish drawing.
· **Linear Shape**: Draw straight-line segments. It can be closed or open. Double click to finish drawing.
· **Closed Shape**: The shape drawn is closed, i.e. the first and last points drawn will be joined.
· **Fill Shape**: The shape will be filled. Forces the shape to be closed.
· **Circle / Ellipse / Rectangle**: Select a geometric shape. If none are selected, the tool will default to drawing a spline or linear shape.

Edit Mode

When the Shapes Tool icon is selected, clicking on an existing shape will present the Shapes toolbar:

- **Lock/unlock** the handles (only relevant to spline shapes): Allows the shape to be modified more flexibly.
- **Remove** the shape from the map.
- **Fit** the map to shape.
- **Center** the map on shape.
- Convert shape to **spline/linear** (not relevant to geometric shapes).
- Make shape **closed/open** (only relevant to lines).
- **Fill** the shape with color.
- Change the shape **style** (for example an ellipse can be a Region or a Country). Note that this may affect the appearance in Viz Artist scenes.

Shortcut keys

When a shape is in edit mode, the following shortcuts keys are available:

- **DELETE** key deletes the shape.
- ***** (asterisk) key centers the map on the shape.

At any time, pressing the **D** key will activate the Shape Tool. When the D key is released, the previously active tool will become active and the shape will be submitted to the Server.

To add a shape to the map

1. Click on the Shapes Tool icon to activate it.
2. Right-click on the Shapes Tool icon. A context menu will appear.
3. Select the kind of shape to draw, for example an ellipse.
4. Drag on the map to create a shape. When the mouse button is released, the shape is submitted to the Viz World Server.

To edit an existing shape

1. Click on the Shapes Tool icon to activate it.
2. Click on the shape you want to edit. A toolbar will appear next to the shape.
3. Use the Shape Tool to modify the shape.

9.2.8   Streets Tool

The Streets Tool can be used to add streets or segments of streets. It uses the data that has been added by the Extra Data Manager.

When the Streets Tool is activated, a red dot will appear when the mouse is hovered over a street. Clicking on the red dot brings up the Streets Tool menu bar.

The Streets Tool menu bar contains:

- **Add Segment**: Allows the user to add segments of the street. Each click on the map adds a segment. Double-click to finish the operation and submit the shape to the Server.
- **Add Street**: Add the selected street to the map.
- **Label Street**: Add just the label without the line.
- **Fit** the map to the street.
- **Center** the map on the street.

Once a street is added to the map, the user can edit it using the Shapes Tool.

9.2.9 Show or Hide Map Features

The Show/Hide Map Features button toggles the features on and off. If they are on, a summary of features is also displayed.

To configure which features will be displayed, click the arrow and select which map features to show.

To modify a feature, you can also hover over the feature on the map to display the tool bar.

> ⚠ **Note:** You can also show or hide individual details, using the Details tool.

9.2.10   Quick Map

The **Quick Map toolbar** allows quick navigation to regions, countries and cities. It works together with the Locator tab to identify the location of the map segment which is currently displayed in the Map Editor window.

- **Q**: Click on the Q icon to filter the drop-down lists and configure which features will be listed in them.
- **Globe**: Provides quick access to regions of the world, for example, Asia, Middle East, Europe.
- **World drop-down**: Select a country
- **Country drop-down**: Select a State or City
- Click on the drop-down **headings** (e.g. *World* or *Australia*) to zoom to the corresponding level (i.e. world or country).
- Type in the text field to **search** for countries, regions or sub-regions.

9.2.11   Locator and Preview

The **Locator-Preview tabs** display the following information:

Locator

- Select an area and the map will zoom to that location

Preview

- If the Map Editor was opened from Viz Artist, Viz Trio or Viz Pilot, the Preview tab will generate a snapshot of the Viz Scene. For Viz Pilot it will only work if a preview server is configured.

  > ⚠ **Note:** The Preview Server URI **must** include the http prefix (e.g http://localhost: 54000). In Viz Pilot 5.7.x and earlier, check the setting in VizPilot under *Options > Preferences > Advanced > preview_server_uri*. In Viz Pilot 6.0 or later, check the setting in the Data Server under *Settings > VCP Parameters > preview_server_uri*. For more information see the section 'To give applications access to the Preview Server' in the Viz Pilot User Guide.

9.2.12 Preset Editor

· Right click on the Locator to display a list of **predefined regions**.

· Add your own presets to this list by right-clicking and selecting **Add Current View as Preset.**
Then enter a name for the preset.

- Edit your presets by right-clicking and selecting **Edit Presets**. In the window that appears, you can rename, reorder, delete, or duplicate the custom list.

9.2.13 Multihop Editor

The Multihop Editor allows users to control the number of hops on a template. For example, if a scene was designed with 2 hops, the user in Viz Trio would be able to add up to 30 hops.

Enable the Multihop Editor

The Multihop Editor is hidden by default, but can be enabled in the following ways:

- If a scene contains a Control Multihop plugin, then when the World Map Editor is opened from Viz Trio or Viz Pilot, it will include the Multihop Editor.
- When a scene in Viz Artist contains the Hops Manager plugin, then pressing the Multihop button will open the World Map Editor, including the Multihop Editor.

Using the Multihop Editor

Once enabled, the Multihop Editor appears on the right-hand side of the World Map Editor, and shows all the hops that are defined. The hops can be reordered by dragging them to the desired place in the list.

Multihop Editing Options

A context menu on the Multihop Editor displays the following options:

- **Cut**, **Copy**, **Paste**, **Duplicate** or **Remove** items in the list.

- **Change Style**: Select one or more hops and change their style. The change will ONLY apply to the selected hops.

> ⚠ **Note:** To change the style of ALL hops, use the **Select stylesheet** button in the Horizontal Toolbar.

- **Change Project**: Select one or more hops and select a new map template file for these hops. The change will ONLY apply to the selected hops.

> ⚠ **Note:** To change the project of ALL hops, use the **Open Project** button in the Horizontal Toolbar.

9.3 World Map Editor Shortcuts

Where you are	Shortcuts you can use
While in detail map editor	Esc - Cancel edits Enter - Save edits
While in detail list editor	Esc - Cancel edits F2 - Start edit Multiply - Fit to detail Divide - Center to detail Minus - Remove detail

Where you are	Shortcuts you can use
While on a list feature	Multiply - Fit to feature Divide - Center to feature Plus - Add feature Minus - Remove feature
While in preset edit mode	Esc - Cancel edits Enter - Save edits
While in shape edit mode	Esc - Cancel edits Enter - Save edits Del - Delete shape Multiply - Fit to shape
While on first look list	Esc - Clear filter
While on main view	Ctrl + O - Open project browser Ctrl + S - Save favorite
While pan tool selected	Ctrl - Zoom tool while key pressed
While zoom tool selected	Spacebar - Pan tool while key pressed
While shape tool selected	Ctrl - Zoom tool while key pressed Spacebar - Pan tool while key pressed
While street tool selected	Ctrl - Zoom tool while key pressed

10 Map Designer

The Map Designer is a component of the Viz World Client (WoC). Map Designer allows you to create map templates similar to those created using Viz World Classic. In comparison with Viz World Classic, Map Designer offers just the core features, which allow you to design stunning maps in no time.

Map Designer shares much of the functionality of the World Map Editor, and as such, all shared features are described in the World Map Editor section, with only the additional features of the Map Designer covered in this section.

> ⚠ **Note:** Currently the Map Designer is only able to work with flat maps.

This chapter contains information on the following topics:

- Getting Started
- Map Designer Toolbars
- Stylesheet Editor

10.1 Getting Started

Once you have the Viz World Client installed you can start the Map Designer and connect to the Viz World Server. Once connected you will be able to open existing design projects, use existing templates, create new templates from existing templates, or create a template from scratch using a blank template.

10.1.1   To start the Map Designer

The Map Designer can be started from the desktop or start menu (i.e. Viz World Design Client), or from the installation directory (`MapsDesignClient.exe`):

- · 32-bit system: `C:\Program Files\vizrt\Common\Maps`
- · 64-bit system: `C:\Program Files (x86)\vizrt\Common\Maps`

10.1.2   To connect to Viz World Server

1. Start the Map Designer
2. Click the Settings button, located on the toolbar.
3. Set the Viz World **Server** hostname. If not specified, the Map Designer will connect to `localhost`.
4. Click Save

10.1.3   To create a map template

1. Start the Map Designer
2. Select one of the following options
   - · **Open Project**: Open an existing project
   - · **From Template**: Starts a new project based on a selection of default stylesheets
   - · **From Existing**: Starts a new project based on an existing project
   - · **Blank**: Start a new project

10.2   Map Designer Toolbars

The Map Designer has two toolbars, and most of the functions are the same as the Map Editor Toolbar. The functions that differ are described in this section.

10.2.1   Horizontal Toolbar

The horizontal toolbar is the same as the Map Editor Toolbar, with the exception of:

- · **New Project**: Create a new map template (see Getting Started)
- · **Open Project**: Open existing map template files.

- **Save Project**: Save the current map template file.
- **Save Project As**: Save the current map template file as a new file.

10.2.2   Vertical Toolbar

The vertical toolbar is the same as the Map Editor Toolbar.

10.3   Stylesheet Editor

The Stylesheet Editor is in many ways similar to working with the Styles Editor in Viz World Classic. You can define styles for land, sea, borders and so on.

This section contains information on the following topics:

- Add and Organize Stylesheets
- Customize Styles
- Default Values
- Land
- Sea
- Miscellaneous
- Extra Data
- Borders

10.3.1   Add and Organize Stylesheets

While working on your template's style sheets you can Add new or existing style sheets from other projects to your own project. In addition you can Organize your own style sheets.

Add

When adding stylesheets you can select one of the template stylesheets, or a stylesheet from an existing project or simply a blank stylesheet:

- **From Template**: Browse for and select one or multiple existing stylesheet templates and add them to your project.
- **From Existing**: Browse or search for stylesheets from existing Projects. Select one or multiple existing stylesheets and add them to your project.
- **Blank**: A new blank stylesheet is added and opened.

Organize

When organizing stylesheets, the stylesheets in the project are listed, and it is possible to perform the operations; Duplicate, Rename, or Delete.

Additional stylesheets can be added using the Add button at the top of the Organize window.

10.3.2 Customize Styles

Use the Style Editor to edit and customize the styles of points, lines and areas. These styles can then be used in your Viz World project.

Open the Style Editor from the Stylesheet Editor toolbar.

Style Editor

Style families are listed on the left, and **default styles** on the right. The Style Editor comes with a predefined list of families and styles that can be used as-is, or can be edited or removed. Drag styles to reorder them or move them from one family to another.

The styles are global to the system and are available in the World Map Editor, based on what is available in the Viz scene. Any style in the system that is not part of the scene will be disabled in the editor, and any style that is part of the scene but is not defined as part of the global styles will be available in the *Others* family.

To create a new style family

1. In the Style Editor, click the **New** button to create a new family, then give it a name

2. Within the family, click the **New Style** button to add new styles

3. Fill in the details for the style:
   a. Type (point, line, area)
   b. Name
   c. Icon: Select a new icon in the file browser
   d. Color, opacity etc. Only possible for Area and Line.

4. Click **Save Changes**

To select a new default style

1. Drag a style from the family list to the default list, and drop it on the desired style.
2. Click Save Changes.

10.3.3 Default Values

Settings which use the default values have a grey square next to them. If the value differs from the default, the square turns white. Click a white square to return the values to default.

10.3.4   Land

The **Land** settings allow you to define the Style of the map and its fill colors, aswell as the Drop Shadow and Relief Shading effects.

Style

When defining land styles you first select whether the map should have a **Synthetic**, **Relief** or **Natural** style.

· **Synthetic** gives the map a basic style, where you can select a single **Fill Color** or four fill colors. If you select four fill colors, no country, adjacent to each other, will have the same color. Both Relief and Natural styles can **mix with Synthetic** utilizing its single or four color option. The **Ice Color** can be set separately.

- **Natural** gives you the option to select which satellite imagery provider to use (e.g. Google Maps, Microsoft Virtual Earth, Digital Globe, Planet Observer, and so on). In addition you can adjust the map's *brightness*, *contrast*, *saturation*, *gamma*, and *tint*.
  If the stylesheet uses either **Google Maps, Digital Globe** or **Microsoft Bing**, you can set which imagery profile to use as default. The profiles provide different imagery sets for the same location. If required, the operator can change the profile from the Map Editor Toolbar when selecting the desired final location.

- **Relief** contour colors work the same way as for Sea. It gives you the option to define colors at varying levels of height (i.e. from 0 to 8000 m.a.s.l.). Clicking below the bar adds a *new handle*. Double-clicking a handle will open a color picker for *setting a color* for that level. Dragging the handle horizontally will *adjust the height parameter*. Dragging the handle vertically will *remove the handle*.

Drop Shadow

Drop Shadow can be added to land, lakes/wide rivers, and narrow rivers. The drop shadow effect also allows you to adjust the angle of the shadow, and its distance and softness (spread).

Relief Shading

Relief shading can be added to land. When enabled you can define how the light will affect the relief by adjusting the highlight (by click and drag). The **Size** and **Intensity** settings will help you control the appearance of the relief texturing on the map.

Refine Relief will add extra detail to the relief. This is especially helpful when zooming in at low levels.

The image below shows a map with Refine Relief enabled and disabled:

10.3.5 Sea

The **Sea** settings allow you to define the color and/or contour colors of the sea, and when using satellite imagery how it should mix with the base and/or contour colors.

Color sets the base color of the sea.

Contour colors work the same way as for Land. It gives you the option to define colors at varying levels of depth (i.e. from 0 to 10000 m.b.s.l.). Clicking below the bar adds a *new handle*. Double-clicking a handle will open a color picker for *setting a color* for that level. Dragging the handle horizontally will *adjust the depth parameter*. Dragging the handle vertically will *remove the handle*. **Opacity** blends the base color with the contour colors. The lower the value, the more of the base color will be shown, and conversely.

Natural sea enables you to select which satellite imagery provider to use (e.g. Google Maps, Microsoft Virtual Earth, Digital Globe, Planet Observer, and so on). In addition you can adjust the map's *brightness*, *contrast*, *saturation*, *gamma*, and *tint*.

Mix with others allows you set the alpha for the mix between the base and/or contour colors and the satellite imagery. It will mix the colors based on whether you are near or far away from sea level. Meaning, when you are close to sea level it will use the near mix setting, and when far away it will use the far mix setting.

10.3.6   Miscellaneous

Projection: Map projection either Marcator or Cylindrical Equidistant (Unprojected).

Global Map Data/Extra Map Data: For **Lakes** and **Rivers** you can select a base color (no alpha) and whether or not *None*, *Major*, *Medium*, *Minor* or *All* lakes and/or rivers should be shown.

For rivers you can also define:

- **Master Size** affects the width of all rivers drawn as lines.
- **Small Rivers** affects the width of rivers which are classified as minor rivers.

- **Max Width (in pixels)** determines the maximum line width at which rivers will be drawn. This is useful if you wish to prevent rivers being drawn as very thick lines as a map zooms in.

When **Local Street Data** is enabled, the data for lakes and rivers can be displayed.

Latitude/Longitude Lines can be enabled/disabled. The color, width and spacing are configurable.

10.3.7 Extra Data

If Local Street Data is used, the **Extra Data** settings allow the various types of roads to be styled.

10.3.8 Borders

The **Border** settings allow you to define the border color and width (in pixels, 0.00 - 10.00 px). You can set colors and width for country and region borders, and coastal lines. In addition you can enable/disable disputed borders. Disputed borders are shown with a dashed line.

11 Map Builder

The Map Builder is a component of the Viz World Client (WoC). Map Builder is used during design in Viz Artist to build maps quickly and efficiently. It is used in conjunction with the Map Builder Plugin scene plugin.

> ⚠ **IMPORTANT!** Prior to using the Map Builder you need To import basic map elements.

In general when creating a map scene your scene will consist of a few basic elements. The elements are built in the following order:

1. Create a scene using the Map Builder plugin (see Getting Started)
2. Choose Scene Type
3. Create a Base Map.
4. Define the Global Hop.
5. Create a Navigator which can be used to create a destination list.
6. Set the map Orientation.
7. Configure the design source and object pool Settings.
8. Use Window to enable or disable a window mask for the scene.
9. Use Global Borders to generate global vector border data based on the settings applied.
10. Refresh the thumbnails when re-launching the Map Builder to make changes (see Toolbar and Menus).

11.1   Getting Started With Map Builder

Once you have installed the Viz World Client you can start Viz Artist and create a scene using the Map Builder Plugin scene plugin. Note that the Map Builder itself will by default connect to the same Viz World Server as Viz Artist. If needed you can switch to another Viz World Server from Map Builder's file menu.

As a first step to work with the Map Builder you can create a scene that only contains the Map Builder Plugin scene plugin. Once created you can launch the Map Builder by clicking the Launch Wizard button. This will open the Map Builder and allow you to Choose Scene Type.

11.1.1   To start creating a scene using the Map Builder

1. Start **Viz Artist**
2. Click **Built Ins** and then the **Scene Plugins** tab
3. Select the **Maps** plugin folder
   - This will show the Map Builder scene plugin

4. Click **Scene Settings** and the **Plugin** tab
5. **Drag and drop** the **Map Builder** plugin onto the Plugin areas placeholder
6. **Save** the scene

- Once the scene has been saved you can open the Map Builder and click the Launch Wizard button to open the Map Builder.

11.1.2 To import basic map elements

1. Start **Viz Artist**.
2. Click **Import** and select **Archives** from the drop-list
3. Navigate to **C:\Program Files\Vizrt\Common\Maps\Archives**
4. Select the **VizWorldGlobalDesigns.via** archive.
5. Click **Import Archive**.

11.2 Choose Scene Type

When launching the Map Builder you will be presented with the following options:

- **Navigator**: Allows you to build a scene with one starting point and up to 32 destinations.
- **Focus on Map**: Allows you to create a static scene with a base map only. Can only be used with flat geometries.
- **1 Destination**: Allows you to build a scene with one starting point and one destination.
- **Map Object**: Allows you to build a scene with one starting point and one destination. The window option is used so that the map only uses part of the screen.
- **Open**: Opens existing map template files.

11.3 Toolbar And Menus

11.3.1 Toolbar

- **New Map Template**: Allows you to create a new map template (see Getting Started)
- **Open**: Allows you to open existing map template files.
- **Save**: Saves the map template file.

- **Save As**: Allows you to save the map template file as a new file.
- **Refresh**: Refreshes the thumbnails. Refreshing thumbnails must be done after manually editing a Map Builder generated scene and when re-launching the Map Builder as all thumbnails of maps (Base Map, Destinations and Orientation) are lost. In order to refresh them press the F5 key, or click the refresh button in the toolbar.

11.3.2 Menus

- The **File** menu contains the same functions as the Toolbar, as well as Exit.
- **Tools** menu contains
    - Refresh thumbnails
    - Map Server Settings: i.e. Viz World Server host name
    - Option to enable/disable the tooltips
- **Help** menu contains links to the About information and the User Guide

11.4 Base Map

Base Map is the Globe/Flat map in a specific style and data. The map created at this level is usually good for country level view.

11.5 Global Hop

Defines the camera's trajectory animation setting. It describes how the navigation animation should be (e.g. map start + 3 destination animations, each "hop" animation based on 5 seconds, with stop points between destinations).

11.6 Navigator

11.6.1 Type

Type defines whether each destination will be of type Geo Position Only, Map - Single Image or Pyramid of Maps.

A *Geo Position Only* destination will only use a Geo Position reference to the navigation. This mode is useful for destinations that are always far away from the base map. No map will be created in this mode (as it will save texture memory).

> ⚠ **Note:** When destination is set to Geo Position Only, it cannot be controlled by an external application such as Viz Trio or Viz Pilot.

Map – Single Image enables operators to control a destination using an external application (either a Map or Pyramid has to be selected). If the selected destination is used for a reference point, and it needs to be controlled, use this type (e.g. a far away starting point).

Pyramid of maps is used when the base map is not suitable for close-ups. A pyramid of maps built around the destination will smoothen the resolution difference between the base map and the destination target.

11.6.2 Destinations

Each destination can consist of map **elements** (labels, regions and miscellaneous map elements).

If destinations are controlled (e.g. by Viz Trio or Viz Pilot) they can be **linked** to each other – to allow the user to easily control multiple destination elements. Linking is *only* a help to the user and has no effect on the scene.

Copying (duplicating) a destination is possible by selecting a destination and clicking the **add** button.

> ⚠ **Note:** The selected destination will not be duplicated if the destination type is *Geo Position Only*.

11.7 Orientation

The Orientation map is displayed in the bottom corner of the screen. It consists of a small map with a marker showing what part of the world is currently being navigated to.

There are three views available:

- Center Map: The orientation map will be moved according to the main map's geographic properties
- Locator: A marker on the orientation map will move according to the main map's geographic properties
- Globe: A globe will rotate according to the main map's geographic properties.

11.8 Settings

Allows the user to specify the design source and object pool path.

Designs source is an option that allows designs to be shared between scenes by using the Object Pool, instead of the in-scene designs.

Object Pool Path: The default object path is `/vizrt/VizWorld/GlobalDesigns`. This option allows users to specify an alternative Viz Graphic Hub or Object Pool folder. A custom Object Pool Path must use the same hierarchy structure as the default object path.

Map Layer: Select whether the scene will use the Front and Main layers, or will only use the Main layer and then apply a Dynamic texture for the overlaid items.

11.9 Window

When this option is enabled the Map Builder will add a window mask to the Viz Scene and also apply the X, Y, width and height values to it.

11.10 Global Borders

This option will enable Borders as vector shapes in the scene.

- *World*: Select whether to create full world vector borders or not
- *Region Data*: Additional regional data up to the resolution selected (Country, Region, SubRegion)
- *Region List*: The regions that will be built are based on the selection in this field.
- *Country Borders:* Select whether to generate Internal Borders, Coastline Boarders or Both

12 Map Editor Classic

The World Map Editor (WME Classic) is a component of the Viz World Client. WME Classic can be integrated with numerous Vizrt products that enables users to select, frame and populate maps and use them in Viz. The WME connects to the Viz World Server and retrieves the map to be used.

This section contains information on the following topics:

- Map Editor Classic
- Using the Map Editor
- Map Name Editor
- Using the Map Name Editor

12.1 Classic Map Editor

The WME window includes the map area, navigation and map editing area, map details area and the map tool bar. The user can select (zoom and pan) a region on the map, or use the search tool to find the requested location. The user can add information to be displayed over the map by selecting objects from the database or by manually marking a place on the map. The added objects are displayed in the Map Details area.

This section contains information on the following topics:

- Map Area
- Navigation and Map Editing Area
- Search Tab
- Explorer Tab

- Extra Data Tab
- Symbols Tab
- Map Tool Bar
- Map Details Area

12.1.1   Map Area

The map area displays the current map and enables the user to modify the map interactively, according to the selected tool in the buttons toolbar and by using the integrated Zoom Options.

Context Menu

- **Guides**: Allows you to display default guides (e.g. safe and title area) or custom guides and/ or images (e.g. logo and background). For more information, see how To add custom guides.
- **Languages**: Defines the language setting for labels. See the Server Configuration tool's Display section and how To create a new language file.
- **Server Priority**: Sets the connection priority given by the Viz World Server. See the Server Launcher Configuration section and the **Enable Priority Login** option. If you are working on scene design using Viz Artist, Viz Artist also needs to be configured (separately). See Viz Artist's Maps Configuration section.

To add custom guides

With custom guides you have three options; two for placing an image as a background or logo and one for placing guides such as title and safe area boxes.

1. On the Viz World Server machine locate and open the **CustomGuides.txt** file under
   - **32 bit**: `C:\ProgramData\Curious Software\Curious World Maps\Settings`
   - **64 bit**: `C:\ProgramData\vizrt\Viz World\Settings`
2. Enter the following to show an image (e.g. logo) on top of the map:
   - **Syntax**: `Type "Title" Ratio Width(%) Height(%) "Filename" Image X(%) Image Y(%) Opacity(%)`
   - **Example**: `Image "Logo" 1.333 80 80 "C:\logo.png" 0 0 75`
   - This will add an image on top of the map, the image will be applied with 75% opacity (alpha is supported).
3. Enter the following to show a background image on top of the map:
   - **Example**: `Image "Background" -1 90 90 "C:\background.png" 5 5 25`

- This will stretch *background.png* to fit the current aspect ratio (-1) with 5% on each side as margin at 25% opacity.

4. Enter the following to add a custom guide to the map:
   - **Syntax**: `"Title" Ratio Width(%) Height(%)`
   - **Example**: `"4:3 Title Safe" 1.333 80 80`
   - Valid width and height values have to be between 50 and 100. Set ratio (width divided by height), or `-1` for current aspect ratio. You can define up to 5 custom guides.

Zoom Options

In the upper left corner of the Map Area there are two rectangular blue shaped buttons that can be used to zoom in and out of the map. In addition it is also possible to use the mouse (left button) and/or in combination with the keyboard.

The zoom options, besides menus and buttons, are:

- Drag and draw a rectangle to **zoom in** to fit.
- Click the left mouse button to **zoom in**.
- Hold down SHIFT to **zoom out**.
- Hold down CTRL to **zoom in** in smaller steps.
- Hold down CTRL and ALT to **zoom out** in smaller steps.

12.1.2 Navigation and Map Editing Area

The navigation area enables the user to locate places by searching the database or selecting a place from the explorer list. When a place is found (or selected) the user can fit the map to the requested area, add information to the map, highlight the region and modify the map.

Using the Results

After conducting a search or using the explorer, the results will be displayed as a list. When an entry is selected, the buttons on the right side of the list will become enabled:

- **Add to map:** Adds the selected entry to the map. The selected entry will be added to the map graphically as defined in the selected map style. A map style defines map symbols, fonts, icons, colors, and so on. For map styles see also Map Tool Bar and the *Map Style* drop-down menu.

- **Center map:** Pans the map to center the selected entry (keeping the current map scale size).

- **Fit to fill:** Centers the map and scales the map to fill the map area.

- **Show details:** Opens the browsing tool, which displays the context information for the selected detail. The context information includes the regions containing the detail (that is country, state and county) and the capital of that country.

12.1.3   Search Tab

The search tab is used for searching the database for a place, using a string or sub string typed in the name text box. The search results can be filtered using the radio buttons and the drop-down list.

Searching is instant (after the first three characters) and optimized according to relevance; hence, if you search for Paris your result will show all places named Paris, but if you search Paris TX you will get Paris in Texas, USA.

If you have street data (see Extra Data Tab) you can also search for crossroads using AND or & (e.g. Broadway AND 44th).

Search Parameters

· **Find All:** When selected it displays all matching entries in the database.
· **Find Visible:** When selected it only displays matching entries visible in the current map.
· **Addr and Cross st.:** Enables the user to search for specific addresses.

- **Type:** Limits the result list according to the selected Type. For example region, capitals, tourist attraction, and so on.
- **Source**: Searches a range of sources.
  - **All**: Searches all sources.
  - **Internal**: Searches the map database and extra data.
  - **Map DB**: Searches the Viz World database.
  - **Extra Data**: Searches all extra data packages bought in addition to the standard installation (see Map DB).
  - **Web**: Searches Yahoo for online point data.

> ⚠ **Note:** Searching for addresses requires licensed street data installed on the server.

12.1.4   Explorer Tab

The explorer tab is used for selecting a location from a list of places derived from the server's database. The list is displayed in a tree format showing countries, regions, cities, and so on.

Explorer Parameters (list filter)

- **Visible:** Only displays location entries visible in the current map.
- **Type:** Limits the search result list to the selected type like region, capitals, tourist attraction, and so on, when one of the entries in the list of available types are selected.
- **Filter:** Filters the search result further.

> ⚠ **Note:** To find New York, type N, then type E, etc. with every character typed in the string filter the list will be smaller.

12.1.5 Extra Data Tab

The Extra Data tab is used for selecting a street from the streets database on the server, and Keyhole Markup Language (KML) files.

> ⚠ **Note:** Streets data requires additional license features and the installation of street data on the server.

Streets

Streets data is available from the Streets node, and are sorted by Motorways, Primary Roads, Main Roads and Other Roads. Use the Filter search to search for streets.

Import KML

Keyhole Markup Language (KML) files can be imported and added to the map. The KML data will be accessible from the Extra Data tab as with street data. By clicking the KML Files node, all the imported KML files will appear as sub nodes. Click one of the imported KML files to open the KML file window the respective file will be file.

KML files currently must be manually imported into the server. Files are placed in the following location:

- **32 bit**: `C:\ProgramData\Curious Software\Curious World Maps\KML`

- **64 bit**: `C:\ProgramData\vizrt\Viz World\KML`

12.1.6   Symbols Tab

Symbols are added using Viz World Classic, and can be imported using the Configuration tool or Viz World Classic.

To add symbols

1. **Start** Viz World Classic, preferably on the maps server.
2. Create or open a map project.
3. From the **Tools** menu, select **Symbols**.
4. In the Symbols dialog box, click the **+** symbol (bottom) to search and select for a symbol.
5. **Close** Viz World Classic.
6. **Restart** the Viz World Server to load the new images.

> ⚠ **Note:** Images should reside on the map server or on a shared drive.

12.1.7   Map Tool Bar

The map tool bar includes a row of buttons controlling the map interactive mode. The map area enables an interactive map selection and manipulation and the map tool bar is used for selecting the map interactive behavior.

Map Tool Options

- **Available Map Stylesheet:** Displays a list of available map styles of the selected template. Select a map style to apply the style's design to the displayed map.
- **View Presets:** Displays a set of view presets. Available options are: The World, United States, N America, S America, Americas, Africa, Asia, Middle East, S Asia, Europe and United Kingdom.
- **Open New Template:** Loads one of the defined templates installed on the server creating a blank map with the template's styles and settings. When pressing this button a confirmation window will open. When confirmed, the template window will open. Select one of the projects in the list and click OK. A new map will appear in the map area using the new template's default styles and settings.
- **Save Favorite**: Save map as a favorite.

> ⚠ **Note:** User favorites will not be synchronized across servers when working with server allocator. When working with multiple servers, synchronizing user favorites can be done as an automated process of replicating the relevant folders. User favorites are stored by default under C:\ProgramData\Vizrt\Viz World\Users\Default\Favorites.

- **Undo button:** Cancels the last change on the map.
- **Redo button:** Cancels the last canceled change on the map.
- **Bird's Eye:** Displays the available imagery Bird's Eye imagery from the Bing Maps Platform. When clicking the button, the imagery for the area of the current map will be displayed enabling the user to select an image for the map.

More >	Quick Map
	Set Location

- **Quick Map:** Opens the Quick Map location browser that enables the user To create a map using the Quick Map location browser.
- **Set Location:** Opens the Set Location dialog which enables the user To set the map location using longitude, latitude and map size values (radius around the defined point).
- **Region Zoom:** Enables the user to click and drag the mouse on the map to create a rectangle surrounding an area on the map (rubber band).
    - The rectangle displays two icons; a cancel icon in the upper right corner and accept icon in the lower left.
    - The rectangle keeps the aspect ratio set for the map unlike regular zoom (see below).
    - Region zoom can be adjusted before accepting the area selection.
- **Zoom:** Zooms into the map on every click on a point in the map centering the clicked point in the Map Area. Another option is to drag and create a selection area. When the mouse button is released, the selected area will become the selected map. Selecting an area using the zoom option does not maintain the aspect ratio.

> ⚠ **Note:** Both Region Zoom and Zoom allows for area selection in the Map Area; however, Region Zoom will maintain aspect ratio and allow the user to cancel the operation after the selection was made.

- **Pan:** Enables the user to click and drag on the map to move the map in the direction of the drag.
- **Pick Feature:** Shows a group of available places from the database as "phantom labels". This feature enables the user To pick a label and add it to the map. The labels will appear over the map only when an entry is selected in the explorer tab or in the search area.
- **Browse Map:** When clicked any click on the Map Area will update the browse window with context information for the clicked position. The context information includes regions containing the position (for example country, state and county) and the capital of the

country.

- **Move Label:** Enables the user To move a label in the Map Area. Map Label enables the user to move the tip and the caption of user-created labels or to rotate them. In other labels only the caption can be moved and rotated.

  > ⚠ **Note:** Rotation of labels in WME will not effect label objects generated by Viz (3D labels). The rotation is noticed only when using labels as part of the map texture.

- **Add Label:** Adds a label at the click point, enabling the user to enter and select a label text and label icon type.

- **Remember label and publish to all users:** When this option is checked, the new label will be added to the database. Whenever the place is selected all the customized labels will be available for selection by the user. When the option is unchecked, the modified label will be used only by the current map.

- **Streets:** Enables the user to select and label streets on the map. Street data must be loaded for this feature to work (see Extra Data Tab).

- **Add Shape:** Adds shapes to the map. Select between points (straight) and bezier (curved). Selecting the Add Shape button also opens a small toolbox for selecting shape designs.

  Available options are:
    - **Area:** Fills the drawn shape, and will also close the line (see Closed Line).
    - **Closed Line:** Allows the user to close the shape without setting the final point (e.g. 2 points will draw a third closing the line with the first point).
    - **Open Line:** Allows the user to draw a line that is not closed.
    - **Delete Last:** Deletes the last drawn line.
    - **Cancel:** Cancels the draw operation.
- **Edit Shape:** Allows the user to edit the shapes and streets added to the map. Streets (roads) can be offset, while shapes can be adjusted using the Point toolbox that appears when the Edit Shape button is selected.

> ⚠ **Note:** Shapes and streets can be edited further using the maps plugins (e.g. 3D Line and 3D Line Manager).

To create a map using the Quick Map location browser

1. Click the More button's Quick Map option in the WME.
2. Select or search for a country in the Country list.
   - The map area will fit to the selected country and the State/Region list will show a list of available regions of the selected country.
   - When a country is selected in the list, the Add to map and Mark Area buttons will be enabled.
3. Select an entry from the list, the County/sub region list will be filled.
4. Click Finish to close the location browser and create the map.

> ⚠ **Tip:** Clicking the Search button switches the Quick Map tool to the search tool mode.

To set the map location

1. Click the Set Location button in the WME to open the Set Location dialog box.
2. Enter the longitude, latitude, and map size radius in miles, kilometers, meters or yards.
3. Click OK to calculate and display the map in the Map Area.

To pick a label and add it to the map

1. Perform a search and select a location.
2. Click the Pick Feature button to display all the phantom labels for the selected area.
3. Click a label to add it to the map.

To move a label

1. Click the drop-down button to open a list of options.
2. Select one of the options and then select a label on the map and move the label around in the graphic display.

12.1.8 Map Details Area

The Map Details area displays a list of all the added locations over the map. The user can modify the map, by selecting one of the added places and the control buttons on the right side of the map details area.

Map Details parameters

- **Style:** Sets or modifies the graphic display representing the selected place on the map. The style selection will affect the highlighting color used to mark the selected place, the label, and so on.
- **Font Size:** Sets the font size used for the label in the graphic display. Font size is only relevant for the display in the editor and for text labels that are exported as part of the map texture; hence, it will not affect the size of labels rendered by Viz.

- **All Caps:** Uses only capital letters in the graphic display when showing the selected place's label.

- **Rename label button:** Opens the Rename Label dialog box that will allow the user to customize and add other labels to the database by entering a new label for the selected place or by selecting an existing label from the list of labels or modifying an existing label.

 - **Remember change and publish to all users:** When this option is checked, the renamed label will be added to the database. Whenever the place is selected, all the customized labels will be available for selection by the user. When the option is unchecked, the modified label will be used only by the current map.

> ⚠ **Note:** The label will be used in the graphic display and in the map details area.

- **Delete place from map:** Removes the selected entry from the map (and from the map details list).

- **Delete all places from map:** Removes all added places from the map (and from the map details list).

12.2 Using The Map Editor

This section describes how to use Viz World's Map Editor (WME) with Viz Artist, Viz Pilot client (which includes how to use Viz Template Wizard and the Newsroom Component), Viz Trio and Viz Weather.

This section contains information on the following topics:

- To test with Viz Artist
- To test with Viz Pilot
- To test with Viz Trio
- To test with Viz Weather

12.2.1   To test with Viz Artist

Viz Artist requires no additional setup as long as the Viz World Client is installed, and the map server settings in Viz Config's Maps section have been activated.

1. Open a map scene
2. Locate and click the **CWMClient** icon in the tree structure to open the CWMClient Editor.
3. In the editor, click the **Viz World Map Editor (WME)** button to open the editor.
4. Search and select a map, and click OK to add a map to the scene

> ⚠️ **Note:** Make sure that **ControlMap** plugins are placed on the same containers as the CWMClients in order for Viz Pilot to be able to change their maps.

12.2.2 To test with Viz Pilot

Viz Pilot's map server parameters are stored on the Viz Pilot database. The parameters can be set or changed using the Viz Pilot client (Options > Preferences > Viz World).

For an operator or journalist to be able to change maps, the map scenes must use the ControlMap plugin. Also, before the scene can be used in the Viz Pilot client or Newsroom Component a map template must be created using Viz Template Wizard.

1. Start Viz Template Wizard
2. Import a Viz Artist map scene to the Viz Template Wizard
   - If a ControlMap plugin is used by the designer an image component will be automatically added to the template
   - A template user clicking the image component will then be able to open Map Editor to select a map
3. The **ImageSources** property should be set to **IsAdvancedCuriousMap**
4. Save the template to a concept

Once the template is stored it can be opened by the Viz Pilot client or Newsroom Component.

1. Start the Viz Pilot client or Newsroom Component, and open the newly created template.
2. Click the image in the template to open the WME.
3. Enter a search criteria (for example London)
4. Select *London City, England* from the list
5. Tick *London City, England*, and click the zoom button (map icon) for England
6. Click OK to close the WME.
7. Save a data element of the template and add it to the playlist.
8. Play or preview the scene on a local Viz Engine renderer to see the map animations.

12.2.3   To test with Viz Trio

Viz Trio's map server parameters are set by the local Viz Engine that Viz Trio uses to render the scenes locally; hence, there is no need to configure Viz Trio.

1. Start Viz Trio
2. Select **Import Scenes** from the drop-list in the Editing window.
3. Locate and import a tutorial scene to create it as a Viz Trio template.
4. Select and double-click to open the newly added template.
5. Click the **Browse Viz World** button to open the editor.
6. Enter a search criteria (for example London)
7. Select London City, England from the list
8. Tick London City, England, and click the zoom button (map icon) for England
9. Play the scene in Viz Trio so see the map animations

12.2.4   To test with Viz Weather

To enable Viz World capabilities add the following entry to the Viz Weather INI file:

```
[CURIOUS]
cwm_enabled=y
simplified=n
```

1. Open a map enabled scene in the editor
2. Click the Map button on the editor toolbar
3. Click the Map icon to select a map
4. Select From Server
      · When selected, a full version of the map editor opens
5. Select a map project
6. Enter a search criteria (for example London)
7. Select London City, England from the result list
8. Enter a new search criteria (for example England)
9. Select England from the result list

10. Adjust the view and style of the map
       · Use the map buttons (lower right) in Viz World Client
11. Click OK to close the map editor.
12. Play the scene in Viz Weather to see the map animations.

12.3 Map Name Editor

The Map Name Editor is a batch feature translation tool meaning that you can use it to edit multiple language translations stored at the Viz World Server.

- **World Server**: Allows you to connect to the Viz World Server using either hostname or IP address. Click the Connect button to connect with the server.

Once logged in you can display all features at four different region levels; World, Country, Region and Sub Region level. However, this depends on the levels available for each country (e.g. the United States of America has all four levels, while Oman only has three levels).

Once you have chosen the regional level you want you can further filter your result or select one or several of the pre-configured layer buttons.

If you right-click the column headers you can display different columns. The standard columns are Display Name, DB Name, Alternate Name, User Name, Abbreviations and Type. In addition you can add you custom language alternatives and choose to display them using the context menu.

See Also

- Using the Map Name Editor

12.4 Using The Map Name Editor

This section describes how to use the Map Name Editor. See the following sections for more information:

- To create a new language file
- To add language specific translations
- To use the new language file

12.4.1 To create a new language file

1. Start Windows Explorer
2. Create a folder named **Languages** in the following location:
   - **32 bit**: `C:\Program Files\Curious Software\Curious World Maps\SharedData`
   - **64 bit**: `C:\Program Files\vizrt\Viz World\SharedData`

3. In the folder you can either place an empty file called **<my language>.mdx** or copy and rename UserNames.mdx (if you already have changed a lot of the label names)

4. Start the **Map Name Editor** executable found under
   - 64 bit: `C:\Program Files\vizrt\Viz World`
5. Edit the new file
   - Your language will be added as a new column
6. Click **Save Changes**

12.4.2   To add language specific translations

1. Start the Map Name Editor
2. Connect to your Viz World Server
3. Right-click and select your language column representing your custom language file
4. Search for the name that needs a language specific translation
5. Enter the translation and click **Save Changes**

12.4.3   To use the new language file

1. Start the **Server Configuration tool** and log on to your Viz World Server
2. Select the Maps' **Display** section
3. Set the Alternate Label Display's first option to be **M-Language** (multi-language)
4. Start for example Viz Artist, create a maps scene and launch the Map Editor (WME)

5. Right-click the map area and select your language from the appearing context menu

> ⚠ **Note:** Setting a language in WME does not affect the language used in Viz Artist.

6. For Viz Artist add/edit the **VizWorld.ini** file under **C:\ProgramData\Vizrt\viz3\Maps** and add the following entry:

```
language=[my Language ID]
```

7. or (dynamically) send the following command to Viz Engine:

```
MAPS LANGUAGE [my Language ID]
```

> ⚠ **Note:my Language ID** refers to the order in the list of languages, English = 0, Norwegian = 1etc. See the above screenshot.

See Also

- Map Name Editor
- Display
- Maps Configuration

13 Photoshop Plugin

The Viz World Photoshop Plugin is used to integrate Viz World and Adobe Photoshop files. Maps created with the Photoshop Plugin will create a new file with separate layers for every feature and detail on the map.

> ⚠ **Note:** The Photoshop Plugin must be installed separately, see Installing Photoshop Plugin.

This section contains the following topics:

- Working with the Photoshop Plugin
- Photoshop Layers
- Viz World Settings in Photoshop

13.1 Working With The Photoshop Plugin

Once the plugin is installed, you will be able to open Map Editor Classic from within Photoshop.

In Photoshop, go to **File > Scripts** and you will see the **Viz World** options.

The options that the plugin adds, are:

- **Viz World Map Editor**
    - Opens Map Editor Classic.
    - Select a TPL, style, and so on, then browse and add details to your map.
    - After making your selections and clicking OK, a new Photoshop file will be created with all the layers of the different features and details on the selected map.
- **Viz World Refresh Map**
    - Opens Map Editor Classic with the selections and map from the previously generated Photoshop file.
    - Modify your selection, add details to the map, and so on.
    - After making your selections and modifications and clicking OK the changes will be applied to the existing Photoshop file instead of creating a new file.
- **Viz World Save As Geotiff**: Save the file as a GeoTIFF file (a TIFF file which includes georeferencing information)
- **Viz World Setting**: Opens the settings window

13.2 Photoshop Layers

The Photoshop Plugin creates 5 layers in your Photoshop file. The following two layers are always created:

- All Layers (a raster image of the final selected map)
- Base Map (a raster image of the land and sea without any selections)

The remaining three layers can be configured in the Viz World Settings in Photoshop window.

13.3 Viz World Settings In Photoshop

To open the Viz World Settings, go to **File > Scripts > Viz World Setting**

- **Server Name**: Viz World Server Host name
- **Layer 1/2/3**: The Photoshop Plugin creates 5 Photoshop Layers. Three of these layers can be configured here by selecting the features that should be included.

14 Open Street Map Downloader

The Open Street Map (OSM) Downloader is a tool for downloading street maps from the Open Street Map initiative.

The street maps are prepared by Vizrt and can be downloaded from the Vizrt FTP at download.vizrt.com. In order to get access you need to sign up for an account. Please contact your local Vizrt representative for more information.

This section contains information on the following topics:

- OSM Downloader Interface
- Working with the OSM Downloader

14.1 OSM Downloader Interface

14.1.1 Vizrt FTP Credentials

- **Username and Password:** Your Vizrt FTP username and password.
- **Remember me:** Allows the tool to remember your username and password for the next OSM download session.
- **Use Proxy**: Enter the Proxy Server hostname, Port, Proxy User and Proxy Password if using a proxy.
- **Connect:** Allows you to connect to the Vizrt FTP and the Viz World Server
- **Refresh:** Allows the Viz World Server to update the street data after the OSM data has been downloaded.

14.1.2 Select Files

- **Breadcrumbs navigation:** Allows you to select the street data you want to add to your download list.
- **Add** ➕: Select a street map from the drop-list and then click the + button to add the item to your download list.
- **Available Files:** Lists the files that are available on the server.

14.1.3 Download

- **Download Queue:** Lists all OSM items ready for download. You can also check/uncheck each download item. If you want to delete items from the queue you simply select an item and press the Delete button or click the right mouse button.
- **Destination folder:** Defines where you want to keep the downloaded data on local disk. Note that the Viz World server expects the files to be in the default folder (see how To configure the OSM Downloader).
- **Download:** Start downloading from ftp to local folder.

14.2 Working With The OSM Downloader

14.2.1 To install the OSM Downloader

The OSM Downloader must be installed alongside the Viz World Server. This is done by installing Viz World Client components on the server.

1. Run the **Viz World Client installer**
2. Select Custom
3. Select the Viz World Server Config component
4. Click Next
5. Click Finish

14.2.2 To configure the OSM Downloader

Before the open street maps can be downloaded and used by your designers you need to configure the Street Data location.

> ⚠ **Tip:** Both tools can be started from: `C:\Program Files\vizrt\Common\Maps`

1. Run the Viz World Server Configuration tool
2. Connect to your map server
3. Select the Maps -> Locations section to configure the Street Data location
4. Run the OSM Downloader tool
5. Set the Destination folder to match the Street Data location

14.2.3 To download open street maps

Before you start to download open street maps you need to have a Vizrt FTP account, aswell as have the software installed and configured.

1. Run the OSM Downloader tool
2. Make sure you have a connection to your map server
3. Enter your Vizrt FTP account credentials and click **Connect**
4. **Browse** and **select** data
5. Click **Add** ➕ to add data to your download queue
6. When done, click **Download**

> ⚠ Tip: Before attempting to connect, make sure the destination folder is configured correctly to match whats configured for Street Data location in Viz World Server configuration, and user has write privilege to that folder.

15 Geographically Referenced Maps

CWMClient plugin produces geographical maps (geo maps). Geo maps are images of maps that are geographically referenced (that is the image contains information about its longitude and latitude).

Geo maps are identified by a little globe icon next to the image icon. Containers that will be placed under the GeoMap container and using geographic data referencing will be placed relatively on the GeoMap.

> ⚠ **Note:** Do not modify the image properties.

Do not scale, rotate or change the position of the image in the image editor. Changing any of these parameters will result in loss of the image's geographical reference.

All modifications should be done in the container properties editor.

The geo map can be placed on any Geometry Object; however, the geographical referencing will not be correct when placed on 3D objects other than Globe. It is recommended, for best geographical referencing results, to use GeoImage, Globe or terrain objects.

16 Viz World Plugin API

The Viz World Plugin API offers an easy to use geo-reference capability when building your own Viz Artist plugins. The API allows you to communicate and manipulate Viz World scenes and get Navigator Plug-in information.

This section contains information on the following topics:

- Working with the API
- Best Practices

16.1 Working With The API

This section contains short descriptions on how to use the API and what it does.

16.1.1 VWPosition

Can be used to position a container based on a longitude/latitude coordinate on a geo-referenced map.

To use VWPosition

1. Add a geo-referenced map on a container (using GeoImage/Globe geometry)
2. Add a child container to the newly created container with a geometry and the VWPosition plugin
3. Changing the longitude/latitude will update the position of the new container

16.1.2 VWMousePosition

Can be used to translate a Mouse position into a longitude/latitude coordinate.

To use VWMousePosition

1. Add a geo-referenced map on a container (using GeoImage/Globe geometry)
2. Add a child container to the newly created container with a geometry and VWMousePosition plugin
3. Click the E button (events button next to the Scene Editor)
4. Click on the map and see that the new container moves to the coordinate

16.1.3 VWNavigatorControl

Can be used to get or set Navigator values.

To use VWNavigatorControl

1. Create a Navigator scene
2. Under the scene's **GeoReferenceMap** container, add a new container with a VWNavigatorControl
3. Clicking the **Update Geo Ref Data** button will read navigator current values
4. Changing one of the plugin's fields will set Navigator values

16.2 Best Practices

When using a geo-reference (*VWGeoref*) object it is best to use a class member that will be initialized in the constructor or only when you would like to explicitly do a refresh, doing so on the ExePerField will impact performance.

The scene object (*VWScene*) has to be initialized in the constructor and has to be freed on the destructor, avoiding to do so will result a performance impact as Viz World's memory consumption will not be freed.

16.2.1 Example

```cpp
class MyPlugin
{
....
private:
    VWScene * m_pVWScene;
}
MyPlugin::MyPlugin()
{
    m_pVWScene = VWScene::AddVWSceneInstance(this);
}
MyPlugin::~MyPlugin()
{
VWScene::RemoveVWSceneInstance(m_pVWScene, this);
}
```

17 Viz World Server REST Support

This section contains a list of searches and functionalities of Viz World Server that can be accessed with a Representational State Transfer (REST) architecture using the atom protocol.

The Viz World Server has the following entry point:

```
http://<vizworldserver>:10301/Directory
```

This section contains information on the following topics:

- Browsing Regions
- Browsing Projects and Favorite Folders
- OpenSearch Support
- Place Finder
- Specify a Bounding Box

17.1 Browsing Regions

Viz World Server allows browsing regions (e.g. administration levels country, admin1, admin2) by returning a feed that represents each region and contains entries for each sub-region (or if none, entries representing towns in that region).

Each entry contains an atom description of the region, a link to its feed, links to towns contained in that region, a link to a map of the region (using the Place Finder functionality shown later) and an XML representation that is used by the Viz World clients.

17.1.1 URLs

The below URL is the **main URL** that returns a feed of all countries.

```
http://<vizworldserver>:10301/Browse
```

The below URL is an example **region URL** that returns a feed containing an entry for each sub-region of the queried region. If no sub-regions exist, a list of towns in that region will be returned.

```
http://<vizworldserver>:10301/Browse?id=91296a0a00000600
```

17.1.2 Parameters

The following describes the main fields (XML tags) of each entry:

- **Id**: Viz World database unique id of the region/town.
- **Title**: Viz World database name of the region/town.
- **Summary**: http text containing feature details - thumbnail, feature type, name, link to map (using Place Finder URL), link to major/minor/both towns of the region (if exists).

- **Content**: Contains an xml representation of the feature, containing information like long/lat, full region description (i.e. "Paris France" for Paris), feature type and more information that the querying application might need.
- **Link (down)**: Contains the same link as the link (alternate). Required by Viz FeedBrowser.

The summary (depicted above) is displayed in browsers like this (circled in red). For more details, see the XML Example below.

17.1.3   Example

```
<entry>
<id>1000000000001200</id>
<title type="text">Belgium</title>
<summary type="html">&lt;table&gt;&lt;tr&gt;&lt;td&gt;
&lt;img src="http://<vizworldserver>:10301/FeatureThumbnail/?
feature=Country"&gt;&lt;/td&gt;&lt;td&gt;Country&lt;br&gt;&lt;a href="http://
<vizworldserver>:10301/PlaceFinder/?Search=(null)"&gt;Get Image&lt;/
a&gt;&lt;br&gt;See Towns:&lt;a href="http://<vizworldserver>:10301/Browse/?
id=71f2d1c100001200&amp;filter=Capital,Town 1m,Town 100k"&gt;13 Major Towns&lt;/
a&gt;&lt;/td&gt;&lt;/tr&gt;&lt;/table&gt;</summary>
<updated>2010-07-07T15:22:39Z</updated>
<author><name>VizWorldServer</name></author>
<thumbnail url="http://<vizworldserver>:10301/FeatureThumbnail/?feature=Country"/>
<link rel="up" type="application/atom+xml;type=feed" href="http://<vizworldserver>:
10301/Browse/"/>
<link rel="self" type="application/atom+xml;type=entry" href="http://
<vizworldserver>:10301/PlaceFinder/?Search=Belgium"/>
<link rel="alternate" type="application/atom+xml;type=feed" href="http://
<vizworldserver>:10301/Browse/?id=71f2d1b900001200"/>
<link rel="down" type="application/atom+xml;type=feed" href="http://<vizworldserver>:
10301/Browse/?id=71f2d1b900001200"/>
<content type="application/atom+xml;type=feed">
   <MapFeature>
   <FeatureID>1000000000001200</FeatureID>
   <Name>Belgium</Name>
   <DBName>Belgium</DBName>
   <AlterName>Belgium</AlterName>
   <Type>Country</Type>
   <GeoPoint>4.466875, 50.259453</GeoPoint>
   <Diameter>280.409729</Diameter>
   <FullDesc>Belgium</FullDesc>
   </MapFeature>
</content>
</entry>
```

17.2   Browsing Projects And Favorite Folders

Viz World Server allows browsing the folders of projects (tpl files) and favorites (cxp files) that are stored in the browser.

A folder feed contains an entry for each sub-folder and project/favorite contained in the folder.

A project feed contains an entry for each stylesheet contained in the browser. A favorite link and project-style link returns an image of the favorite/style.

17.2.1 URLs

```
http://<vizworldserver>:10301/ProjectsFolder/
http://<vizworldserver>:10301/FavoritesFolder/
```

Each favorite/project/style entry also contains a thumbnail tag that contains a URL of a thumbnail image of the project/favorite/style for use by Viz FeedBrowser. The thumbnail URL is also included in the summary of the entry, for use by browsers.

17.3 OpenSearch Support

Viz World Server supports using OpenSearch to search features in the server database, plugins and web.

17.3.1 URLs

OpenSearchDescription URL:

```
http://<vizworldserver>:10301/OpenSearchDescription
```

OpenSearch template:

```
http://<vizworldserver>:10301/OpenSearch?q={searchTerms}&pw={startPage?}
&visible={viz:visible?}&filter={viz:filter?}&source={Internal/All/MapDB/ExtraData/
Web}
```

Example URLs:

```
http://<vizworldserver>:10301/q=Paris&filter=Capital&source=MapDB
http://<vizworldserver>:10301/q=Salem&filter=Town 10k
```

17.4 Place Finder (Server)

Viz World Server allows receiving maps of locations/features, in the same way as the Place Finder plugin. This can be used by Escenic or any other web application, or for demonstrations of Viz World.

Example URLs:

```
http://<vizworldserver>:10301/PlaceFinder/?
Longitude=40.0&Latitude=40.0&FrameMapBy=Country&AddRegions=Full
http://<vizworldserver>:10301/PlaceFinder/?
Search=USA&MapWidth=1000&MapHeight=500&AddSearchLabel=1
```

17.4.1   Parameters

Most parameters are taken from the configuration server (and stored in registry). Upon first use (or if missing in registry) the default values below are used. For parameters that are not stored in the registry, use the default values below.

- **ProjectName**: Desired project (default is VizDefProject.tpl)
- **Style**: Desired stylesheet
- **MapWidth**: Sets the width of the map (default is 512)
- **MapHeight**: Sets the height of the map (default is 512)
- **Longitude, Latitude**: Defines the center of the map if Search is empty (default is 0.0, 0.0)
- **Search**: Desired feature name
- **AddSearchLabel**: If search is used, adds the found label to the map.
- **DefaultMapSizeDeg**: Size of map to be retrieved in degrees (used when FramMapBy = DefaultMapSize)
- **FrameMapBy**: Can be DefaultMapSize, Country, Admin1, Admin2 or Search
- **PlaceText**: Add text label to map (if not empty)
- **FullDescription**: Displays full-description feature labels (i.e. "Paris France" for Paris)
- **AddRegions**: Can be Disabled, FrameOnly, FrameAndBelow or Full
- **ReturnImage**: 1 for image (default), 0 for representing xml

17.5   Specify A Bounding Box

With this feature, users can use the rest API to return map features within a specific bounding box.

17.5.1   URL

Base URI

```
http://<vizworldserver>:10301/Browse?" class="external-link">http://<vizworldserver>:
10301/Browse?
```

URL Template

```
http://<vizworldserver>:10301/Browse?left={value}&right={value}&bottom={value}
&top={value}&filter={FilterTerms}&maxAnswers={value}
```

Parameters

- **Bounding box values**:

- left, right, bottom, top, or
- west, east, south, north
- **Filter**:
  - all
  - Capital
  - Town 1m
  - Town 100k
  - Town 10k
  - Town 1k
  - Town
  - Tourist Attraction
  - Reserve Or Park
  - Region Name
  - Physical Area Name
  - Physical Water Name
  - River Name
  - Mountain Name
  - Region Capital
- **MaxAnswers**: (optional) default 500

17.5.2 Examples

```
http://<vizworldserver>:10301/Browse?left=0&right=0.5&bottom=51&top=51.5&filter=Town
10k,Town 1k
http://<vizworldserver>:10301/Browse?left=0&right=0.5&bottom=51&top=51.5&filter=all
http://<vizworldserver>:10301/Browse?
left=-2&right=1.5&bottom=51&top=55.5&filter=River Name
http://<vizworldserver>:10301/Browse?left=0&right=0.5&bottom=51&top=51.5&filter=Town
10k,Town 1k&maxAnswers=50
```

18 Viz World Classic

This chapter introduces Viz World Classic (VWC) which is the classic design tool for map templates used by the Viz World Client (WoC) and thereby Vizrt's control applications. Viz World Classic is an alternative to Viz World Client's Map Designer.

> ⚠ **Note:** This chapter will not cover all aspects of map design using Viz World Classic; however this chapter will explain important elements to note when creating a basic map template using Viz World Classic.

Viz World Classic is a design tool with a database back-end, used for the creation of branded maps. By extending it with a server, it can provide real-time, branded map imagery to several clients embedded within Vizrt's control applications. Templates created using Viz World Classic or the Map Designer can be dynamically accessed through Vizrt's control applications using the WoC.

Viz World Classic has access to a comprehensive vector based database that includes regions, cities, roads, rivers, and so on. The vector data is supplied to Vizrt under license from Bartholomew Mapping (a division of Harper Collins publishers). VWC also includes global 1km relief data in the DEM (Digital Elevation Model) format. The DEM data is provided by the United States Geological Survey (USGS). Essentially, VWC uses the best mapping data available and is a full animation and compositing system.

This section contains information on the following topics:

- Project Template
- Styles Editor
- Markers
- Map Projection
- Map Position and Project Area Offset
- Layer Stack and No Animation

See Also

- Map Designer
- Viz World Classic User Guide

18.1 Project Template

It is good practice to place **all** template (TPL) files in a single static location.

The recommended location is:

- **32 bit**: `C:\ProgramData\Curious Software\Curious World Maps\Users\Default\Projects`
- **64 bit**: `C:\ProgramData\vizrt\Viz World\Users\Default\Projects`

This folder and any sub-folders are automatically scanned for TPL files when the Map Server is launched.

> ⚠ **Note:** The template location should be exactly the same on Viz World Server and any Viz World Classic design systems. If the paths are not identical it may well break the link to any image elements, e.g. Markers.

18.1.1 To open a project template

1. Select **Open...** (CTRL+O) from the **File** menu.
2. Select **Project Template (*.tpl, *.tpt, *.cgt)** from the **Files of type** drop-list.
3. Select the template file and click **Open**.

18.1.2 To save a project template

1. Select **Save** (CTRL+S) from the **File** menu.
2. Select **Project Template (.tpl)*** from the **Save as type** drop-list.
3. Enter a filename, and click **Save**.

18.2 Styles Editor

Using the Viz Curious Maps (CM) Styles Editor, users can choose to modify an existing default Style Sheet or create a new one.

The user has the ability to define and fully customize all of the available map data elements via the CM's Styles Editor. For example, the user can set region colors, select any font (TrueType only), assign any static image (images with alpha are supported) as a marker, modify shadow settings, change relief scale and lots more!

The map Style Sheets defined within the CM Styles Editor are then saved as Project Templates (TPL files). Each Project Template can include any number of Style Sheets. These Project Templates can then be accessed via Viz World's Map Editor (WME) within other Vizrt products, such as Viz Artist, Viz Trio, Viz Pilot, and so on.

18.3 Markers

Many users work with customized Markers; hence, image files can be imported to Viz World Classic (VWC) from any location. VWC will create a Relative or Absolute file path to the actual image file (depending on its distance from the TPL). If VWC cannot locate an image file it will replace it with a 'missing material' red X.

It is good practice to place all Markers in a single static location, as opposed to multiple folders on a local computer and/or network.

The default location is:

- **32 bit**: `C:\Program Files\Curious Software\Curious World Maps\Markers`
- **64 bit**: `C:\Program Files\vizrt\Viz World\Markers`

> ⚠ **Note:** When exporting a map related Viz Artist scene archive it is important to also include the TPL files and any referenced image files (used for Markers, and so on).

18.4   Map Projection

An **essential** setting for 3D globe building in Viz Artist is To set the map projection to an equidistant cylindrical projection (also known as equi-rectangular or geographic projection). When

using the map on a 3D globe in Viz Artist it will give the right (or more correct) representation of the world.

> ⚠ **Note:** In Viz Artist vertex mapping should be used when creating 3D globes.

18.4.1   Wrong and correct projection

Using the wrong projection within Viz Artist, for example, with the Map Tiler plugin to build a 3D globe, will produce a distorted projection.

18.4.2   To set the map projection

1. Select the **Properties** tab.
2. From the **Projection** drop-list select the **Cylindrical Equidistant** projection.
3. Select "The World" from the **View** drop-list (lower-right corner) to check that the map is a flat and not a globe view of the World.
4. Click **Apply**.

> ⚠ **Note:** This test also works well via the WME in Viz Artist, and so on.

18.5   Map Position And Project Area Offset

Within Viz World Classic (VWC) there are two sizes to be aware of, the **Project Size** and the **Map Size**. Both of these sizes have their own specific purpose and can have different values; however, if the sizes are different or if the Map Position does not match the Project Area exactly, the map will not look right when used in Viz Artist, Viz Trio, Viz Pilot, and so on. Even a minuscule offset will break the map.

> ⚠ **Example:** The Map Rectangle Tool (on the vertical toolbar) allows the user to freely move the map around and can easily move the map out of position.

To avoid the issue entirely, one should delete the Map Layer and add a new one. This automatically adds a map that fits the current Project Size, but note that it will be using the Globe projection and requires correction.

18.5.1 To set the project size

1. Select **Project Settings** from the **File** menu.
2. In the **Project Settings** dialog box set the **Width** and **Height** parameters.
3. Click **OK** to confirm the new project settings.

18.5.2 To set the map size

1. Select the **Properties** tab on the **Properties** panel.
2. Select the **Transform** options, and set the same **Size** (X and Y) that was used To set the project size.
3. Press **Enter** to confirm and update the map.

18.5.3 To add a new layer

· Select **Add Layer** > **Map** from the **Layer** menu.

18.6 Layer Stack And No Animation

To avoid problems with the template (TPL) file, it is good practice to ensure that only one layer is present in the Layer Stack. It is also important to remain at frame 1 in the timeline and refrain from adding any animation keyframes.

19 Frequently Asked Questions

This section contains some of the frequently asked questions concerning the use of Viz World Client and Server.

I can connect Client A to the map server, client B is able to ping the map server, but Client B still has no connection to the map server. What is wrong?

- Sometimes, a machine is not accessible to all other computers in the network by its hostname.
- For example, if there are two clients, Client A & Client B, and the Viz World Server and the Server Allocator running on the MapServer machine, Client A might resolve MapServer to the IP 192.168.1.100, but Client B might not resolve it to the same IP, or might not resolve it at all because ClientB is on another subnet or for any other given reason.
- Both clients can access the MapServer if it was defined as 192.168.1.100 or MapServer.company.domain.
- A frequent problem is therefore that users might write in Client B's Viz Config the IP 192.168.1.100, and in Client A's Viz Config MapServer (because that is the address each can resolve); however, this will result in that the Server Allocator will return to both clients the same hostname that was specified in the Server Launcher Configuration tool and therefore only accessible to ClientA.
- In other words, in the field of ControlledMapServer, the hostname/IP that is specified has to be known to all clients and the Server Allocator machine.

I have problems loading my map scenes in Viz Trio?

- Map scenes often use a large amount of texture memory; hence, this will take time to load and might cause Viz Trio's local preview channel to time out.
- In Viz Trio it is possible to adjust the Viz Engine Connection Timeout for the local preview channel.
- Click the Config button, and under the Miscellaneous section select Local Viz Renderer, and set the Viz Engine Connection Timeout parameter.

> ⚠ **Note:** There is no such setting for the Viz Pilot client as the Viz Pilot client itself does host the Viz process for local preview

What are the Digital Globe proxy and firewall configuration settings?

- If you need to use a proxy, remember to set your Proxy Server settings.
- All communication to Digital Globe servers goes through https to `services.digitalglobe.com` because https encrypts the entire request (i.e. both header and body) .
- Ask your IT department to allow communication to the following Digital Globe server address: `205.166.175.85.`
- See also Digital Globe cache settings.

What are the Microsoft Bing Maps proxy and firewall configuration settings?

- If you need to use a proxy, remember to set your Proxy Server settings.

- All communication to Microsoft Bing Maps servers goes through http (SOAP and regular HTTP GET) on port 80.
- Any sub-domain of virtualearth.net should be
- accessible to the Viz World Server and Viz World Classic application. For example: dev.virtualearth.net, t1.tiles.virtualearth.net, t3.tiles.virtualearth.net etc.
- See also Bing cache settings.

The server cannot find the dongle

- Run as administrator.
- Make sure you are not using Windows Remote Desktop. Instead, you can use Remote VNC or Team View.

Are orthographic cameras supported?

Orthographic cameras are not currently supported by Viz World.